

CARL A. HOUY
510 PATTERSON BUILDING
DENVER, COLORADO 80202
TELEPHONE 303 - 825-6902



RECEIVED

AUG 29 1974

COLORADO OIL & GAS CONS. COMM.

ARTHUR M. GUIDA
WALTERS NO. 1
NE/SE Section 11, T9N, R54W,
Logan County, Colorado
WASHDOWN

August 2, 1974

Ran production casing as follows:

95 jt. 5½" O.D. LT&C R-3 used	3928.56'
41 jt. 5½" O.D. ST&C R-2 used	1274.57'
<u>136 jt.</u>	<u>5203.13'</u>
Difference in KB	6.00'
Total	<u>5209.13'</u>


Set at 5209' with 150 sax 50-50 Pozmix with 3% salt added.
Bumped plug with 1500# - released pressure - float held.
Scratchers: 5190-5165'.
Centralizers: 5205', 5185' and 5160'.

August 4, 1974

Swabbed hole down to 4500'.
Perforated at 5185-91' with 3 - 90 gram jets per foot.
Swabbed hole down - no recovery.
Acidized perforations with 250 gallons of 15% HCL acid.
Pressured to 900# - no fluid entry.
Pressured to 1400# - no leak off.
Pressured to 1800# - broke back to 600#.
Displaced acid at 1/2 BPM.
Recovered 126 barrels on swab down (casing capacity).
Next hour recovered 3 barrels water.

August 5, 1974

Overnight fillup - 1600' of water - no show of gas or oil.
Will plug and abandon.
Ran tubing in hole and laid down in singles.
Move off equipment.



Carl A. Houy

file