

December 7, 1977

RECEIVED

DEC 9 1977

COLD. U.S. MAR. CONS. COMM.



00215945

To Whom it may Concern;

This is to certify that I set the following plugs in the following manner:

Alminex Bonanza 27-1 Section 27, T7N, R78W

11-10-77 Fill hole with drilling mud

25 sx @ 5400-5500 base of 7"

25 sx @ 1750-1850 top of 7"

25 sx @ 370- 470 base of 9-5/8"

25 sx @ surface, cut off below plow depth, and weld plate with description stamped.

✓ Alminex Bonanza Koop 7-1 Section 7, T7N, R77W

11-8-77

25 sx @ 3475-3600 (set with rig, 11-8-77)

25 sx @ 3230-3330 (set with rig, 11-8-77)

25 sx @ 2000-2150 (set with rig, 11-8-77, left mud in hole)

11-27-77

25 sx @ 1000-1100 across stub of 7" @ 1100 and covered base of 9-5/8 @ 1089.

25 sx @ surface, cut off below plow depth, and weld plate with description stamped.

Yours very truly,

W. J. Rippy Jr.

WJR/111