




00723849

**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompletion

☐

Notice of Intention to Abandon Well

☒

Other

☐

(Check appropriate space)

LEASE NAME George W. Wheeler WELL NO. 1FIELD _____ WILDCAT X COUNTY RouttLOCATION NE SE Section 6 Township 7N Range 85W Meridian 6th
(Quarter Quarter)1980 feet from S Section Line and 660 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

To confirm telephone conversation of 10-5-60, by and between Mr. Tom Jones, Kingwood Oil Company, and Mr. Doug Rogers, Colorado Oil & Gas Conservation Commission, it is proposed to pull all casing and plug well as follows:

T.D., 1750'.

Fill hole with heavy mud, 1750-1660'

25 sacks of cement 1660-1615'

Heavy mud 1615-1000'

47 sacks of cement 1000- 940'

Heavy mud 940- 50'

60 sacks of cement 50- 0'

Will install permanent marker in surface.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT -7 1960

Date

Director

Company Kingwood Oil Company Date 10-5-60

First National Building

Address Oklahoma City, Oklahoma Phone No. CE 6-3771

By

(Signature)

Title Chief Clerk