


file



075-05698

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



99999999

API

(Indicate nature of data by checking below)

Notice of intention to drill	<u>X</u>	AJJ
Notice of intention to change plans		DVR
Notice of date for test of water shut-off		FJK
Report on result of test of water shut-off		OPS
Notice of intention to re-drill or repair well		HHM
Notice of intention to clean out well		AH
Statement of shooting		JJD
Statement of perforating		FILE
Notice to pull or otherwise alter casing		
Notice of intention to abandon well		
Report of work done on well since previous report		

Following is a (notice of intention to do work) November 23, 19 54
~~(report of work done)~~ ~~(on land)~~ on Colorado State Land
~~(patented)~~ described as follows:

Colorado	Logan	Wildcat
State	County	Field
<u>#3</u>	<u>NW SW 34</u>	
State	SW $\frac{1}{4}$ Sec. 23	T. 8 N., R. 51 W. 6th P.M.
(Well No.)	(Lease) (Sec. and $\frac{1}{4}$ Sec.)	(Twp.) (Range) (Meridian)

The well is located 990 ft. (N) of S Line and 330 ft. (E) of W.
Line, SW $\frac{1}{4}$ Sec. 23.

The elevation above sea level is est. 4153 ft. from ground (Obtained by reference to nearby dryhole well data.)

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- Objective sands: D sand, estimated at approx. 4340'
J sand, estimated at approx. 4453'
- Proposed casing: Surface casing-- 10 3/4", 32 lbs., 200', 100 sacks cement.
Production casing, if required-- 5 1/2", 14 and 15 lbs.
- Estimated total depth: 4500'
- Type tools: Rotary
- Will core D and J sands and take drill stem test in each if warranted; will run Schlumberger log to total depth; will plug and abandon if dry hole or will run production casing if producer

Approved: NOV 29 1954
A. J. Jersin
Director

Company Cwm-Alpin
Address Box 743, Casper, Wyoming
By _____
Title _____

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.



00226911