



COLORADO
LOGAN COUNTY
FLEMING ✓

PETROLEUM INFORMATION
DENVER CASPER
ROCKY MOUNTAIN
OIL INFORMATION

Twp 8N-50W
Section 16
NE NE SW
(2310 N/S 2310 E/W)

OPR: H. C. Arnold

WELL #: 1 State

ELEV: 4354 KB.

*TOPS: Log-Sample

Niobrara 3699

Ft. Hays 3951

Greenhorn 4242

D Sand 4441

J Sand 4548

DSTS. & CORES:

DST 4432-55, Op 30 min,
shut in 15 min, rec
135' mud; DST 4565-
75, Op 15 min, gas
immediately no fluid,
recovered, flowed est 3-4
MCF gas per day, FP
1000#, SIP 1175#, Thru
3/4" choke, 4671 TD. Perf.
16 shots 4570-74.

SPUD: 12-6-52

TD: 4671

CSG: 8-5/8" @ 210 w/150
5 1/2" @ 4671 w/150

PERF:

4570-74 w/16 shots.

COMPL:

PB:

BROD. ZONE:

INIT. PROD: Flowed 4,500 MCF gas per
day, CP 700#, Completed
as a shut in gas well. ✓

✓ "J" SAND DISCOVERY - NEW FIELD."

"CORRECTED CARD - WITH ADDITIONAL DATA."

3-25-54

*For Electric Logs on Rocky Mountain Wells—Ask Us!

~~Close file~~

7/21/66.

Leave elec. log in
file.

Leather