

**FORM**  
**5**Rev  
10/14**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402262634

Date Received:

**DRILLING COMPLETION REPORT**

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10633

Contact Name: Logan Siple

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

Phone: (303) 579-2174

Address: 1801 CALIFORNIA STREET #2500

Fax:

City: DENVER State: CO Zip: 80202

Email: logan.siple@crestonepr.com

API Number 05-123-47172-00

County: WELD

Well Name: Hingley

Well Number: 1K-18H-A167

Location: QtrQtr: NENE Section: 18 Township: 1N Range: 67W Meridian: 6  
FNL/FSL FEL/FWL

Footage at surface: Distance: 513 feet Direction: FNL Distance: 517 feet Direction: FEL

As Drilled Latitude: 40.057010 As Drilled Longitude: -104.925810

GPS Data:

Date of Measurement: 07/18/2019 PDOP Reading: 3.1 GPS Instrument Operator's Name: Scott Porter  
FNL/FSL FEL/FWL\*\* If directional footage at Top of Prod. Zone Dist: 460 feet Direction: FNL Dist: 173 feet Direction: FEL  
Sec: 18 Twp: 1N Rng: 67W\*\* If directional footage at Bottom Hole Dist: 467 feet Direction: FSL Dist: 127 feet Direction: FEL  
Sec: 18 Twp: 1N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 08/10/2019 Date TD: 11/04/2019 Date Casing Set or D&amp;A: 11/05/2019

Rig Release Date: 11/06/2019 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 12372 TVD\*\* 7495 Plug Back Total Depth MD 12337 TVD\*\* 7495

Elevations GR 5058 KB 5081

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

MWD/LWD, CBL (IND in 123-07367)

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	42	0	122	48	0	122	VISU
SURF	13+1/2	9+5/8	40	0	2,590	970	0	2,590	VISU
1ST	8+1/2	5+1/2	20	0	12,351	1,420	2,558	12,372	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,677		NO	NO	
SHANNON	5,285		NO	NO	
SHARON SPRINGS	7,429		NO	NO	
NIOBRARA	7,479		NO	NO	
FORT HAYS	8,058		NO	NO	
CODELL	8,183		NO	NO	

## Operator Comments:

TPZ footages are estimated; well is not completed. Estimated completion Q2 2020.

Open Hole Logging Exception - No open-hole logs were run; Log used for the Exception was an Induction Log run on the Hingley Farms 1, 123-07367

Cased-hole Pulsed Neutron Log was run on the Hingley 1F-18H-A167 well, 123-47171; per BMP on APD; Rule 317.p exception granted for the well.

GPS locations were taken on preset conductors.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Lindsey Organ \_\_\_\_\_

Title: Regulatory Coordinator \_\_\_\_\_

Date: \_\_\_\_\_

Email: lindsey.organ@crestonepr.com \_\_\_\_\_

### Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
402274162	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
402274160	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
402274151	PDF-MWD/LWD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
402274153	LAS-MWD/LWD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
402274154	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
402274157	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
402274159	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

