



OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS

216

File

(Indicate nature of data by checking below)

Notice of intention to drill.....  
Notice of intention to change plans.....  
Notice of date for test of water shut-off.....  
Report on result of test of water shut-off.....  
Notice of intention to re-drill or repair well.....  
Notice of intention to clean out well.....  
Statement of shooting.....  
Statement of perforating.....  
Notice to pull or otherwise alter casing.....  
Notice of intention to abandon well..... ☒  
Report of work done on well since previous report..... ☒

December 20, 1951  
Following is a (~~notice of intention to do work~~) (On land)  
(report of work done) (patented) described as follows:

Colorado	Logan	Wildcat			
State	County	Field			
1	Mc Roberts	SW $\frac{1}{4}$ Sec 6	8 N	52 W	6 PM
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)	(Twp.)	(Range)	(Meridian)

The well is located 2310 ft. (N) of S line and 2310 ft. (E) of W line  
(S) (W)

The elevation above sea level is 4084 ft. (Rotary Drive Bushing)

Details of Plan of Work: (State names of and expected depths to objective sands:  
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
ing points, and all other important proposed work.)

The above described well was plugged on December 6, 1951 by placing the following  
cement plugs through open ended drill pipe, using HOWCO equipment:

20 Sacks @ 4770 (Calculated to fill to 4720)  
20 Sacks @ 4653 (Calculated to fill to 4543)  
20 Sacks @ 150 (Calculated to fill to 105)

The top of the surface casing was plugged with cement and a regulation marker of  
4  $\frac{1}{2}$ " O D pipe extending four feet above the ground was erected. The location  
will be leveled and the pits will be filled as soon as weather permits.

Approved: DEC 26 1951

State Oil Inspector  
DIRECTOR

Company TRUE AND BROWN

Address Box 203, Casper, Wyoming

By

Title Partner

Submit reports of proposed work, for approval, on this form in Duplicate.