

PP1-095-0607
OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well..... X
Report of work done on well since previous report.....

December 5, 1951

Following is a (notice of intention to do work) (~~On-land~~)
(~~report of work done~~) (patented) described as follows:

Colorado	Logan	Wildcat			
State	County	Field			
1	Mc Roberts	SW 1/4 Sec 6	8 N	52 W	6 PM
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)	(Twp.)	(Range)	(Meridian)

The well is located 2310 ft. (N) of S line and 2310 ft. (E) of W line.
(37) (47)

The elevation above sea level is 4084 ft. (Rotary Drive Bushing)

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

The above described well was spudded November 22, 1951.
10 3/4" 32.75# casing was cemented at 139' with 100 sacks of cement using Halliburton Oil Well Cementing Company equipment. The well was drilled to a total depth of 4934, penetrating the following formations:

Top Niobrara Chalk	3802'
Top Ft Hayes Limestone	4130'
Top Greenhorn Limestone	4398'
Top 'D' Sand	4643'
Top 'J' Sand	4770'

A Schlumberger Electric survey was run from 139' to 4934', two copies of which are attached. As no commercial shows of oil or gas were encountered we plan to plug and abandon this well by placing the following cement plugs through open ended drill pipe, using Halliburton Oil Well Cementing Company equipment:

DEC 26 1951
Approved: 20 sacks @ 4770 (Calculated to fill to 4720)
20 sacks @ 4643 (Calculated to fill to 4593)
20 sacks @ 150 (Calculated to fill to 105) TRUE AND BROWN

State Oil Inspector
DIRECTOR

Address Box 203, Casper, Wyoming

By

Title Partner

Submit reports of proposed work, for approval, on this form in Duplicate.

