

**FORM**  
**5**Rev  
10/14**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402244287

Date Received:

**DRILLING COMPLETION REPORT**

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10459

Contact Name: Kamrin Ruder

Name of Operator: EXTRACTION OIL &amp; GAS INC

Phone: (720) 9747743

Address: 370 17TH STREET SUITE 5300

Fax:

City: DENVER

State: CO

Zip: 80202

Email: kruder@extractionog.com

API Number 05-014-20756-00

County: BROOMFIELD

Well Name: Livingston

Well Number: S19-25-4N

Location: QtrQtr: NWSE

Section: 7

Township: 1S

Range: 68W

Meridian: 6

FNL/FSL

FEL/FWL

Footage at surface: Distance: 2332 feet

Direction: FSL

Distance: 1474 feet

Direction: FEL

As Drilled Latitude: 39.978563

As Drilled Longitude: -105.039929

GPS Data:

Date of Measurement: 11/18/2019

PDOP Reading: 1.4

GPS Instrument Operator's Name: JAYME HOBIN

FNL/FSL

FEL/FWL

\*\* If directional footage at Top of Prod. Zone

Dist: 2461 feet

Direction: FSL

Dist: 1378 feet

Direction: FWL

Sec: 7

Twp: 1S

Rng: 68W

FNL/FSL

FEL/FWL

\*\* If directional footage at Bottom Hole

Dist: 510 feet

Direction: FSL

Dist: 1305 feet

Direction: FWL

Sec: 19

Twp: 1S

Rng: 68W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 06/06/2019

Date TD: 07/09/2019

Date Casing Set or D&amp;A: 07/10/2019

Rig Release Date: 11/14/2019 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 21250

TVD\*\* 8110

Plug Back Total Depth MD 21245

TVD\*\* 8110

Elevations GR 5318

KB 5347

Digital Copies of ALL Logs must be Attached per Rule 308A

☒

List Electric Logs Run:

CBL, MUD, MWD, (RESISTIVITY 014-20753)

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	42	0	80	100	0	80	VISU
SURF	12+1/4	9+5/8	36	0	1,626	570	0	1,626	VISU
1ST	8+1/2	5+1/2	20	0	21,245	3,437	290	21,245	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,901		NO	NO	
SUSSEX	5,295		NO	NO	
SHANNON	5,806		NO	NO	
SHARON SPRINGS	8,460		NO	NO	
NIOBRARA	8,496		NO	NO	

Operator Comments:

The TPZ footages are estimates calculated through Directional Plotting Software—from where the production string (5 ½" casing) is greater than or equal to 150' south of the center line of section 7, Township 1S, Range 68W. The actual footages will be submitted with the Form 5A.

Alternative Logging Program- No open hole resistivity log with gamma ray was run on this well. Resistivity ran on Livingston S19-25-2C (014-20753)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Kamrin RuderTitle: Drilling Technician

Date: \_\_\_\_\_

Email: kruder@extractionog.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
402244364	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
402280128	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402259022	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402280116	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402280117	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402280118	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402280125	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

