

FORM
5

Rev
10/14

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400715470

Date Received:

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type Final completion Preliminary completion

OGCC Operator Number: 69175 Contact Name: Cassie Gonzalez
Name of Operator: PDC ENERGY INC Phone: (303) 860-5800
Address: 1775 SHERMAN STREET - STE 3000 Fax: _____
City: DENVER State: CO Zip: 80203 Email: Cassie.Gonzalez@pdce.com

API Number 05-123-37640-00 County: WELD
Well Name: Maxey Well Number: 24O-232
Location: QtrQtr: NWSE Section: 24 Township: 5N Range: 65W Meridian: 6
FNL/FSL _____ FEL/FWL _____
Footage at surface: Distance: 2346 feet Direction: FSL Distance: 2468 feet Direction: FEL
As Drilled Latitude: 40.383860 As Drilled Longitude: -104.610770

GPS Data:

Date of Measurement: 07/09/2014 PDOP Reading: 2.2 GPS Instrument Operator's Name: Devin Arnold
FNL/FSL _____ FEL/FWL _____

** If directional footage at Top of Prod. Zone Dist: 2119 feet Direction: FSL Dist: 1824 feet Direction: FEL
Sec: 24 Twp: 5N Rng: 65W

** If directional footage at Bottom Hole Dist: 2173 feet Direction: FSL Dist: 1962 feet Direction: FWL
Sec: 19 Twp: 5N Rng: 65W

Field Name: WATTENBERG Field Number: 90750

Federal, Indian or State Lease Number: _____

Spud Date: (when the 1st bit hit the dirt) 05/29/2014 Date TD: 06/09/2014 Date Casing Set or D&A: 06/12/2014

Rig Release Date: 06/28/2014 Per Rule 308A.b.

Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

Total Depth MD 11018 TVD** 6718 Plug Back Total Depth MD 10961 TVD** 6718

Elevations GR 4636 KB 4651 Digital Copies of ALL Logs must be Attached per Rule 308A

List Electric Logs Run:

CBL, MWD (DIL in 123-16756 and 123-19493)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+3/4	9+5/8	36	0	939	840	0	942	VISU
1ST	8+3/4	7	26	0	7,142	695	110	7,142	CBL
1ST LINER	6+1/8	4+1/2	13.5	60	11,006	725	6,927	11,018	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,527				
SUSSEX	4,197				
SHARON SPRINGS	6,470				
NIOBRARA	6,673				

Operator Comments:

Shannon formation is not present.
Gas kick caused well to TD approximately 89' short of plan.
Open hole logging exception, no open hole logs were run on this pad. APD was approved with no logging BMPs or exceptions.
Corrections on CBL made by operator due to vendor losing large database files in a truck fire.
TOC comments from our Engineer: 7" TOC, 11.5# lead with jumping amplitude and VDL showign signs of bonding. Lower cement weight, 32 bbls returned.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cassie Gonzalez

Title: Regulatory Technician Date: _____ Email: Cassie.Gonzalez@pdce.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
402281228	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
402255002	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402254966	LAS-CBL 1ST RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402254967	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402254997	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402254998	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402255003	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Returned to draft for AOC settlement.	09/12/2016

Total: 1 comment(s)

