




OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS  
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Schreiber WELL NO. 1

FIELD Last Chance WILDCAT COUNTY Washington

LOCATION SW SW Section 28 25 Township 3S Range 56W Meridian 6th Princ.  
(Quarter Quarter)

670 feet from S Section Line and 648 feet from W Section Line  
N or S E or W

(DETAILS OF WORK)

9 5/8" casing cement at 95'.

5 1/2" casing cemented at 5055', perforated 4978'-4982'. PBD 5008'.

Propose to fill hole with gravel to 4970' and dump 15 sx. cement plug at this point. Cut and pull casing from lowest depth possible. Place 10 sx. cement plug at base of surface casing and 5 sx. cement plug on top.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

MAR 19 1962

Date March 16, 1962  
Director [Signature]

Company Consolidated Oil & Gas, Inc. Date March 16, 1962

Address 2112 Tower Bldg. Phone No. AM 6-1306

By [Signature] Title Chief Engineer  
(Signature)