



00380838

123.5994

Nebraska Drillers
COMPANY Glen Perkins Oil Inc.

WELL & No 1 Beard

LOCATION O. SE NW Sec. 27-12N-56W

COUNTY Weld STATE Colorado

DATE Elev. 4951kb
4941gr

Tested or Cured Interval

DRILLING TIME

INTERVAL	DESCRIPTION	MIN →	20
6000-10	Sh, gy fiss, silty w/sh, lt gy bent w/scat siltst gy shly, glau.		
10-20	Sh and siltst as ab.		
20-30	Sh as ab w/scat free bent and pyr.		
30-40	Sh and siltst as ab.		
40-50	Sha as ab w/scat ls as ab w/abd free bent w/siltst gy glau v. shly cal.		
50-60	Sh as ab w/scat ls as ab w/abd free bent.		
60-70	Ls gy to gy br, silty, sdy, shly, sl glau w/shas ab.		
70-80	Sh as ab w/scat ls as ab.		
80-90	As ab.		
90-6100	Sh, gy to gy blk, fiss, silty w/siltst, cal shly.		
6100-10	Ls, gy br, hrd dns, micro-xln, no por NS w/sh as ab.		
10-20	Sh, dk gy to lt gy, some silty some bent w/ls as ab w/ abd pyr.		
20-30	Sh as ab w/ scat ls as ab.		
30-40	As ab w/abd pyr.		
40-50	Sh as ab w/much bent w/tr ls. br litho.		

50-60	
60-70	Sh, gy to gy blk, fiss w/ecat ls as ab w/abd pyr.
70-80	As ab.
80-90	Sh, vari-shades gy, fiss med hrd, some lt gy sft bent w/abd pyr.
90-6200	As ab w/scat siltst gy wt shly sl glau.
6200-10	Cir. @6207 SS, br, f.g., fri, p to f sort, br oil stn, yellow grn fluor.
10-20	(Pipe correction down the hole 5', started coring at 6212')
20-30	
30-40	
40-50	Sh, gy to gy blk, silty w/siltst gy, shly, glau.
50-60	SS, gy wt, f.g., f.top. sort, fri, sub ang, app wet NS w/sh and siltst as ab.
60-70	SS and sh as ab. abd ed.
70-80	SS, gy wt, v.f.g. NS as ab w/sh, gy to gy blk, carb, some silty w/siltst, gy.
80-90	SS, gy wt, f.top. g., fri, f.to p. sort, sub ang, sl glau, f p and p, NS w/sh and silt as ab.
90-6300	Sh, gy to gy blk, fiss, silty w/ss as ab some w/br cast no fluor.
6300-10	Sh, gy to gy blk, fiss, silty w/ss as ab.
10-20	Sh and siltst as ab w/ecat as ab.
20-30	Sh, vari-shades of grey to gy blk silty w/ecat sd as ab.
30-40	Sh and siltst as ab.
40-50	As ab.

