



00380836

123.5994

Nebraska Drillers  
COMPANY Glen Perkins Oil Inc.

WELL &amp; No 1 Beard

LOCATION C SE NW Sec. 27-12N-56W

COUNTY Weld STATE Colorado

DATE Elev. 4951kb  
4941gr

Tested or Cured Interval

DRILLING TIME

INTERVAL	DESCRIPTION	0 MIN →	20
5650-60	Sh, gy br, speck, cal w/sh, gy, fiss silty some aft bent w/abd pyr.		
60-70	As ab.		
70-80	Sh, gy br, speck, cal, as ab w/sh, gy fiss, silty as ab w/abd pyr.		
80-90	As ab.		
90-5700	Ls, wt, chky, no por, NS w/sh as ab.		
5700-10	Ls as ab w/abd br speck cal sh as abw/sh gy to gy blk fiss.		
10-20	As ab w/abd pyr.		
20-30	Ls, gy to gy br to wt, chky w/sh as ab.		
30-40	As ab w/ abd pyr.		
40-50	Ls and sh as ab.		
50-60	As ab w/siltst gy wt, shly, sdy, glau, NS.		
60-70	As ab.		
70-80	Siltst as ab w/lb as ab.		
80-90	Siltst or silty ss as ab w/abd pyr.		
	Sh, gy to gy blk, fiss, silty, some		



5900-10	Sh and siltst as ab.
10-20	As ab.
20-30	Sh, lt gy to dk gy, some silty some bent w/ abd pyr.
30-40	Sh as ab.
40-50	Sh as ab.
50-60	Sh, vari-shades g as ab w/ scat ls, br xln w/ siltst gy al glau.
60-70	As ab.
70-80	Sh and siltst as ab.
80-90	Sh, pred lt gy, bent w/ sh gy silty w/ scat siltst gy wt.
90-5900	Sh and siltst as ab, w/ scat br cal xls.
5900-10	Sh as ab.
10-20	As ab.
20-30	Sh as ab w/ ls gy wt to br silty chly.
30-40	As ab.
40-50	Sh as ab w/ ls some silty as ab. some wt to br al chly dns litho no por no show.
50-60	Sh and ls as ab.
60-70	As a b.
70-80	Sh as ab w/ scat ls as ab.
80-90	As ab.
90-6000	Sh, gy to gy blk, fiss, al silty.

