

OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....  
Notice of intention to change plans.....  
Notice of date for test of water shut-off.....  
Report on result of test of water shut-off.....  
Notice of intention to re-drill or repair well.....  
Notice of intention to clean out well.....  
Statement of shooting.....  
Statement of perforating.....  
Notice to pull or otherwise alter casing.....  
Notice of intention to abandon well..... X  
Report of work done on well since previous report.....

Following is a (notice of intention to do work) (On land) \_\_\_\_\_ October 25, 1951  
(~~report of work done~~) (patented) described as follows:

Colorado	Logan	Wilcat
State	County	Field
1 Beltzer	28, SW	12 North 53 West 6th P.M.
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of South Line and 2310 ft. (E) of the West Line. (SW) (NW)

The elevation above sea level is 4620 ft. K.B.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Wildcat test well drilling at 5798' in Lakota formation. Will be drilled to top of Morrison, expected at 5850', at which point it will be plugged and abandoned. 10 3/4" surface casing set at 292'. Top of Niobrara 4475'; Timpas 4770'; Carlile 4845'; Greenhorn 5040'; Muddy Sand 5317'; Dakota 5426'; Lakota 5675'. Extra heavy mud will be pumped in hole from total depth to base of surface casing at 292'. 20' cement plug will be pumped in well from 292' to 272'. Heavy mud will be pumped in well from 272' to 20' and cement plug from 20' to surface. As this is a wheat field no pipe will be cemented above the surface to mark the location as this would interfere with the cultivation.

Approved: OCT 26 1951

State Oil Inspector

Director

Company PLAINS EXPLORATION COMPANY

525 University Bldg.

Address Denver 2, Colorado

By Russell H. Volk

Title President

Submit reports of proposed work, for approval, on this form in Duplicate.