

OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....  
 Notice of intention to change plans.....  
 Notice of date for test of water shut-off.....  
 Report on result of test of water shut-off.....  
 Notice of intention to re-drill or repair well.....  
 Notice of intention to clean out well.....  
 Statement of shooting.....  
 Statement of perforating.....  
 Notice to pull or otherwise alter casing.....  
 Notice of intention to abandon well.....  
 Report of work done on well since previous report. X

Following is a (~~notice of intention to do work~~) (On land) October 26, 1951  
 (report of work done) (patented) described as follows:

Colorado Logan Wildcat  
 State County Field  
 1 Beltzer 28, SW 12 North 53 West 6th P.M.  
 (Well No.) (Lease) (Sec. and  $\frac{1}{4}$  Sec.) (Twp.) (Range) (Meridian)  
 The well is located 330 ft. (N) of South and 2310 ft. (E) of the  
West Line. ~~(S)~~ ~~(W)~~

The elevation above sea level is 4619 ft. K.B.

Details of Plan of Work: (State names of and expected depths to objective sands:  
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
 ing points, and all other important proposed work.)

Wildcat test well drilled to total depth of 5834', where it was  
 plugged and abandoned. Top of Morrison Formation 5830. Extra heavy  
 mud was pumped in hole from 5834' to base of surface casing at 292'.  
 20' cement plug was pumped in well from 292' to 272'. Heavy mud was  
 pumped in well from 272' to 20' and cement plug from 20' to surface.  
 As this is a wheat field no pipe was cemented above the surface to  
 mark the location because of interference with cultivation. The work  
 on this test well was under the supervision of Charles Todd, Drilling  
 Superintendent for Sterling Drilling Company who drilled the test.

Approved: NOV 1 1951

*[Signature]*  
 State Oil Inspector  
 Director

Company PLAINS EXPLORATION COMPANY  
525 University Building  
 Address Denver 2, Colorado  
 By *[Signature]*  
Russell H. Volk  
 Title President

Submit reports of proposed work, for approval, on this form in Duplicate.