

**State of Colorado**  
**Oil and Gas Conservation Commission**  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
402239255

**APPLICATION FOR PERMIT TO:**

☒ **Drill**      ☐ Deepen      ☐ Re-enter      ☐ Recomplete and Operate

Date Received:  
12/03/2019

TYPE OF WELL   OIL ☒   GAS ☐   COALBED ☐   OTHER: \_\_\_\_\_  
Refiling ☒  
ZONE TYPE   SINGLE ZONE ☒   MULTIPLE ZONES ☐   COMMINGLE ZONES ☐   Sidetrack ☐

Well Name: Green Teal Fed      Well Number: 34-27-7HN  
Name of Operator: MALLARD EXPLORATION LLC      COGCC Operator Number: 10670  
Address: 1400 16TH STREET SUITE 300  
City: DENVER      State: CO      Zip: 80202  
Contact Name: Erin Mathews      Phone: (720)543 7951      Fax: ( )  
Email: emathews@mallardexploration.com

**RECLAMATION FINANCIAL ASSURANCE**

Plugging and Abandonment Bond Surety ID: 20170115

**WELL LOCATION INFORMATION**

QtrQtr: SESW      Sec: 34      Twp: 8N      Rng: 60W      Meridian: 6  
Latitude: 40.612876      Longitude: -104.081474  
Footage at Surface: 500 Feet      FNL/FSL FSL 1802 Feet      FEL/FWL FWL  
Field Name: WILDCAT      Field Number: 99999  
Ground Elevation: 4923      County: WELD  
GPS Data:  
Date of Measurement: 08/23/2017      PDOP Reading: 1.5      Instrument Operator's Name: Ian Carabajal  
If well is ☐ Directional      ☒ Horizontal (highly deviated)      **submit deviated drilling plan.**  
Footage at Top of Prod Zone:      FNL/FSL      FEL/FWL      Bottom Hole:      FNL/FSL      FEL/FWL  
600      FSL      2085      FWL      600      FNL      2085      FWL  
Sec: 34      Twp: 8N      Rng: 60W      Sec: 27      Twp: 8N      Rng: 60W

**LOCAL GOVERNMENT INFORMATION**

County: WELD      Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below.      ☒ Yes      ☐ No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.      ☒

The local government siting permit type is: WOGLA

The local government siting permit was filed on: 05/10/2018

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

WOGLA18-0058 submitted 5/10/18, approved 5/23/18.

## LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.  
(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 8 North, Range 60 West, 6th PM  
Section 34: E2, SW4

Total Acres in Described Lease: 480 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 4719 Feet

Building Unit: 4719 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 491 Feet

Above Ground Utility: 470 Feet

Railroad: 5280 Feet

Property Line: 500 Feet

School Facility: 5280 Feet

School Property Line: 5280 Feet

Child Care Center: 5280 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 263 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 600 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: \_\_\_\_\_

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1153	1280	Sec 27 & 34 - All

## DRILLING PROGRAM

Proposed Total Measured Depth: 16051 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 54 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	43	0	80	50	80	0
SURF	12+1/4	9+5/8	36	0	1555	425	1555	0
1ST	8+1/2	5+1/2	20	0	16051	2525	16051	0

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

This Form 2 is being submitted as a refile of API # 05-123-46184.  
Distance to nearest well is 263' to Green Teal Fed 34-27-6HC

There have been no new buildings constructed and no changes to the surrounding land use, well construction plans, or mineral lease description. The well site has been constructed. The Green Teal Fed 34-27-15HN (API: 05-123-46177) and Green Teal Fed 34-27-16HN (API: 05-123-46182) have been drilled.  
This location is not in a buffer or exception zone, so no notices are required under Rule 305.

As per the COGCC Refile Guidance Document dated March 20, 2017, no new plats or directional plans are required as the locations of the proposed wells have not moved. There are also no changes to the Surface & Minerals, casing/cementing program, or Offset Well Evaluation. All previously submitted notices, Surface Use Agreements, and letters are also still valid.

The Cultural Distances information is unchanged but has been updated to include School Facility information not submitted with the original permits but included in Google Spreadsheet bulk upload in June 2019.

Local Government Information has also been added.

BMP's have been updated to reflect current standards.

This application is in a Comprehensive Drilling Plan ☐ No ☐ CDP #: \_\_\_\_\_

Location ID: 453517

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Justin Garrett

Title: Regulatory Analyst

Date: 12/3/2019

Email: regulatory@ascentgeomatics.c

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved:  \_\_\_\_\_

**Director of COGCC**

Date: 1/29/2020

Expiration Date: 01/28/2022

**API NUMBER**

05 123 46184 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
Drilling/Completion Operations	Operator shall comply with Notice to Operators: Interim Reclamation Procedures for Delayed Operations (dated January 5, 2017).
Drilling/Completion Operations	If conductors are preset, operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016).
Drilling/Completion Operations	<p>1) Submit Form 42 online to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad.</p> <p>2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.</p> <p>3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.</p> <p>Bradenhead Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.:</p> <p>1) All: Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation.</p> <p>2) Delayed completion: 6 months after rig release, prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation.</p> <p>3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.</p>
Drilling/Completion Operations	Operator acknowledges the proximity of the listed offset well(s). Operator agrees to comply with the DJ Basin Horizontal Offset Policy to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, submit Form 42(s) ("OFFSET MITIGATION COMPLETED") for the mitigated well(s), stating that appropriate mitigation was completed prior to the hydraulic stimulation of this well. Offset wells to mitigate: 05-123-05510, DOTY-FEDERAL 1-B, Option 3 05-123-05518, DOTY-FEDERAL 1, Option 3 05-123-05519, FEDERAL 1, Option 3 05-123-07078, DOTY-FEDERAL 1, Option 3 05-123-08700, FEDERAL-DOTY 14-22, Option 3 05-123-11448, GOVERNMENT DOTY 1, Option 3 05-123-11557, GOVERNMENT DOTY 2, Option 3 05-123-20097, HOFFMAN 34-10, Option 1 05-123-20902, HOFFMAN 34-1, Option 1

## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Blowout Prevention Equipment ("BOPE"): A double ram annular preventer will be used during drilling.
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
3	Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on the pad will be logged with an open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a Cement Bond Log with Gamma-Ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.

Total: 3 comment(s)

## Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.  
[http://cogcc.state.co.us/documents/reg/Policies/Wildlife\\_Notice.pdf](http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf)

## Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
402239255	FORM 2 SUBMITTED

Total Attach: 1 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	01/27/2020
Permit	Permit review complete.	01/27/2020
Permit	Following additional analysis arising out of the Objective Criteria, the Director determined that this application meets the standard for the protection of public health, safety, and welfare and the environment, including wildlife resources set by SB 19-181. The Objective Criteria Review Memo (Doc# 1347807) can be found in the document file for Location ID 453517.	01/27/2020
Permit	Distance to Nearest Well is incorrect.  With operator concurrence, the following was corrected: Spacing Order Number was corrected to 535-1153. Distance to nearest well was corrected to 263 ft.	01/08/2020
Permit	Passed completeness.	12/04/2019

Total: 5 comment(s)