




1230978



OIL AND GAS CONSERVATION COMMISSION
DRY NOTICES AND REPORTS OF WELLS

OIL & GAS
CONSERVATION COMMISSION

12N-56W

(Indicate nature of data by checking below)

Locate Well Correctly

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well XX
- Report of work done on well since previous report _____

		26	
			4

Notice to do work Land: Fee and Patented
 Report of work done State Lease No. _____

Colorado Weld Wildcat
 State County Field

1-B McEndaffer SE 26 12N 56W
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 660 Ft. (N) of Section Line and 660 Ft. (E) of Section Line.
 (S) (W)

The elevation above sea level is 4819 Ft. K.B.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Plugging Report

Placed 25 sacks cement through drill pipe @ top of J-Sand 6185.
 Placed 25 sacks cement @ top of D-Sand 6079.
 Filled hole W/heavy mud to bottom of surface casing @ 120'.
 Placed wood plug and 15 sacks of cement @ 120'.
 Filled hole W/mud to 30'-Placed wood plug and 10 sacks of cement @ 30'.
 Filled surface casing W/cement to bottom of cellar.

Dietler-Olson-Seeligson & Strain Drilling Company

McEndaffer 1-B



Approved: MAR 11 1955

Date 3-10-55

Company Dietler-Olson-Seeligson & Strain

Address 508 Mile High Bldg.-Denver, Colo.

A. J. Strain
Director

By A. J. Strain

Title Partner

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

Subscribed and sworn to before me this 10th day of March 1955.
My commission expires September 9, 1958.

Notary Public Pat Kessler

