

COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

- Notice of intention to drill \_\_\_\_\_
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well X
- Report of work done on well since previous report \_\_\_\_\_

Following is a (notice of intention to do work) October 15 19 54  
(~~report of work done~~) (patented) described as follows:

Colorado State	Weld County	Long Field
<u>2</u> (Well No.)	<u>Ella Long</u> (Lease)	<u>NW/4 Sec. 24</u> (Sec. and 1/4 Sec.)
		<u>12N</u> (Twp.)
		<u>56W</u> (Range)
		<u>6 PM</u> (Meridian)

The well is located 330 ft. (N) of South and 330 ft. (E) of West of NW/4  
(S) (W)

The elevation above sea level is 4911 ft. D.F.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

1. The above described well has declined in oil production to 1 barrel per day plus 60 barrels of water. Production is from the "D" sand.
2. It is desired to plug and abandon the well since our operations during the past year have proved to be unprofitable. The "D" sand was acidized with mud acid and fractured. These treatments failed to stimulate a sustained increase in oil production.
3. The well has the following amounts of casing in place:
 

10-3/4"	29#	573'	300	sax cement
5 1/2"	15.5#	6,260'	200	sax cement
4. The well will be plugged in accordance with the general rules and regulations of the Oil & Gas Conservation Commission, State of Colorado. Please indicate any special instructions you wish to be followed in the abandonment procedure.

Approved: OCT 19 1954  
[Signature]  
Director

Company J. M. Huber Corporation  
Address Box 831, Borger, Texas  
By [Signature]  
Title Petroleum Engineer

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.