


COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



87-10

OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

- * Notice of intention to drill _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____

Following is a (notice of intention to do work) June 25, 19 53
(~~report of work done~~) (patented) described as follows:

Colorado State Weld County Wildcat Field

2 (Well No.) Long (Lease) NW 1/4 Sec. 24 (Sec. and 1/4 Sec.) 12 N (Twp.) 56 W (Range) 6th P.M. (Meridian)

The well is located 330 ft. (N) of S line and 330 ft. (E) of W line
of NW 1/4, Sec. 24-12N-56W (C SW SW NW) ground
The/elevation above sea level is 4901 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

1. We propose to drill a well at the above location; said well to be drilled to and into the basal section of the "J" sand of the Dakota series expected to be encountered at an approximate depth of 6,200 feet, unless commercial production is encountered above the foregoing objective.
2. We will set, at an approximate depth of 550 feet, 10-3/4", 29# Armco slipjoint, range 3, surface casing and cement solid.
3. In the event commercial production is found, we will run 5 1/2" production casing to the top or through the producing horizon and cement the production casing with a minimum of 200 sx.
4. Attached is copy of Powers Elevation Company's plat showing exact location and ground elevation. As soon as the rig is on location, elevation of the Kelly Baking will be furnished your office. — 4910'
5. All work will be done in conformance with the Rules and Regulations approved by the Oil and Gas Conservation Commission of the State of Colorado and effective January 9, 1952. Timely reports will be submitted to the State Oil Inspector.

Approved: JUN 26 1953
[Signature]
Director

Company J.M. HUBER CORPORATION
Address Box 2098 Denver, Colorado
By [Signature]
Leo Hantz
Title Division Landman

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.