


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator UTAH SOUTHERN OIL COMPANY Field MAY Wildcat _____
Lease Name GERRY Well No. 3 County WELD
Location NE SE Section 30 Township 12N Range 56W Meridian 6th
(Quarter Quarter)
1980 feet from N Section line and 660 feet from W Section Line
N or S E or W

TOTAL DEPTH 6455'DATE OF PLUGGING 4/25/59

DETAILS OF WORK

PUSHED PLUG TO 5618', DUMPED 5 SACKS CEMENT FROM 5618 to 5578', DUMPED ROCK FROM 5578 to 5575', DUMPED SAND 5575 to 5563', DUMPED ROCK 5563 to 5560', DUMPED 5 SACKS CEMENT 5560 to 5520', WORKED CASING, SPOTTED OIL @ 1000', 1307' and 1715', WORKED CASING, SHOT OFF SAME @ 1419', PULLED CASING, SET ROCK BRIDGE @ 329', DUMPED 10 SACKS FROM 329 to 300', MUDDERED HOLE TO 16', RUN 5 SACKS TO SURFACE AND PLACED MARKER TO CEMENT CAP.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date June 26, 1959

Director

Company UTAH SOUTHERN OIL CO.

1825 FIRST NATIONAL BANK BLDG.

Address DENVER, COLORADO

By

Henry E. McQuinn

(Signature)

Date

Phone No. AM-6-3173Title Prod Supt.