

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED
MAY 28 1965

OIL & GAS
CONSERVATION COMMISSION



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Don M. Rounds Company Field Cliff Wilcat
Lease Name UPRR - Ayres Well No. 4 County Logan
Location NW SE Section 29 Township 12N Range 54W Meridian 6th
1980 (Quarter Quarter) *1980*
1320 feet from S Section line and 1320 feet from E Section Line
N or S E or W

TOTAL DEPTH 5,889 feet DATE OF PLUGGING 4-12-65

DETAILS OF WORK

Ran sand to 5,720 feet, dumped 5 sacks of cement to 5,682 feet. Shot off casing at 4,541 feet, pulled same. Mudded hole to 130 feet, dumped 10 sacks of cement to 98 feet, mud to 13 feet, ran 5 sacks of cement to base cellar. Welded on cap.

*11/4/65 Checked loc. Plugged OK.
Jm*

*EX
Oil
Prod.*

DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: _____ Date JUN 1 1965
Director *W. Rogers*
Company Don M. Rounds Company Date 5-27-65
Address 924 Petroleum Club Bldg. Phone No. 623-0296
Denver, Colorado
By *Don M. Rounds* Title Owner
(Signature)
Don M. Rounds