


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

00623383

PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Don M. Rounds Company Field Cliff Wildcat
Lease Name UPRR-Ayres Well No. 2 County Logan
Location NE SE Section 29 Township 12N Range 54W Meridian 6th
1980 (Quarter Quarter)
1320 feet from S Section line and 660 feet from E Section Line
N or S E or W

TOTAL DEPTH 5,882 feetDATE OF PLUGGING 4-12-65

DETAILS OF WORK

Ran sand to 5,718 feet, dumped 5 sacks of cement to 5,673 feet, shot off casing at 4,800 feet, pulled same. Mudded hole to 135 feet, dumped 10 sacks of cement to 108 feet, mud to 13 feet, ran 5 sacks of cement to base cellar. Welded on cap.

*11/4/65 Checked loc. Plugged OK.
Hm*

DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

*EX
oil
Prod.*

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUN 1 1965

Director

Company Don M. Rounds CompanyDate 5-27-65Address 924 Petroleum Club Bldg.
Denver, ColoradoPhone No. 623-0296

By

(Signature)

Don M. Rounds

Title Owner