

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

JUN 23 1966

OIL & GAS  
CONSERVATION COMMISSION

## SUNDRY NOTICES AND REPORTS ON WELLS

## INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☒Other ☐

(Check appropriate space)

LEASE NAME H. S. AYRES WELL NO. 5FIELD Cliff WILDCAT COUNTY LoganLOCATION SE SW Section 28 Township 12N Range 54W Meridian 6th  
(Quarter Quarter)  
660 feet from South Section Line and 1980 feet from East Section Line  
N or S E or W

## (DETAILS OF WORK)

This was was shut in April 16, 1956, completed as shut in gas well. We have tested well over past two years and gas has been depleted from other wells in the reservior. We propose to plug and abandon as per State regulations.

We propose to shoot off casing at approximately 4600', spot 15 sacks cement in top of pipe stub, 15 sacks in base of surface casing and 10 sacks in top of surface casing, weld 1/4" Steel plate over top of surface pipe 18" below ground level and clean location.

DVR	
WRS	
HHM	
JAM	
FJP	✓
JJD	✓
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

JUN 27 1966

Company SINCLAIR OIL & GAS COMPANY Date May 20, 1966Address Box 9 Fort Morgan, Colo. Phone No. 867-5434Date                       
Director *W. Rogers*By *A.B. Parker* Title Field Supt.  
(Signature) (A.B. Parker)