



AS CONSERVATION COMMISSION
MENT OF NATURAL RESOURCES
IE STATE OF COLORADO

File in triplicate for Patented and Federal lands.
File in triplicate for State lands.

RECEIVED

DEC 9 1974

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> Dry Hole		5. LEASE DESIGNATION AND SERIAL NO. COLO. OIL & GAS CONS. COMM.	
2. NAME OF OPERATOR Great Western Drilling Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR Suite 2170, 1600 Broadway Denver, Colorado 80202		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface SE NW Sec. 6, T-7-N, R-91-W 1945' FNL & 2262' FWL of Sec. 6 At proposed prod. zone		8. FARM OR LEASE NAME Beckett	
14. PERMIT NO. 74-873		9. WELL NO. #1	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6692' Ground 6706' KB		10. FIELD AND POOL, OR WILDCAT Wildcat	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 6, T-7-N, R-91-W 6th P.M.	
		12. COUNTY Moffat	13. STATE Colorado

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data


NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input checked="" type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work 11-13-74

- Spud 10-27-74, ran 13 jnts, 11 3/4", K-55, 47# casing set at 530' KB
- Drilled a 9 7/8" hole to a total depth of 5716' driller, 5705' logger.
- Total depth was approx. 350' into the Mesaverde sand.
- DST #1 (Lance formation) 2671'-2856' could not reach bottom.
DST #2 2671'-2856' - 0/15", SI 60", 0/60", SI 120"; recovered 2490' of fluid, being 600' water cut mud, and 940' gas & mud cut water, and 900' gas cut fresh dirty water. PreFP 565-828, ISIP 1054, 2nd FP 900-1045, FSIP 1064. Sample chamber 2100 cc fresh water.
- Log Tops: Ft. Union 920', Lance 2169', Lewis 3414', Mesaverde 5370'
- Following plugs were set: 50 sx 2800-2900'; 50 sx 2550-2650'; 15 sx 515-545'; 10 sx top of surface
- P&A 11-13-74 Rig released 7:00 p.m. 11-13-74.



18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE District Geologist

DATE 12-6-74

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

DIRECTOR

DEC 10 1974



00221895

Al McGlone
Great Western

1-Beckett

1945 F N
2262 F W

SE NW

Correct footage

10/18/74

Jules

