



00251237

081-6721

PROPOSED PLUGGING METHOD

WELL: 791-3505 No. 1 Cockrell Oil Corporation

LOCATION: SWNW S35-T7N-R91W Moffat Co., Colorado

PERFORATIONS OPEN: 3271' to 3292'

PLUGGING PROCEDURE:

1. Scrape casing at cast iron bridge plug seat.
2. Set CI bridge plug 50' above perfs.
3. Mix and spot thru tubing 150' cement plug on top CIBP.
4. Pull tubing out of hole, set 50 foot cement plug at surface.
5. Dig out and cut off casing 4 feet below surface. Weld on cap and backfill.

8/12/92

well status = VP

JDL