

**FORM  
INSP**Rev  
X/15**State of Colorado  
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

01/21/2020

Submitted Date:

02/05/2020

Document Number:

692200196

**FIELD INSPECTION FORM**Loc ID 325354 Inspector Name: Chollett, Shannon On-Site Inspection ☐ 2A Doc Num: \_\_\_\_\_**Operator Information:**

OGCC Operator Number: 74500

Name of Operator: REYNOLDS\* NOEL

Address: BOX 356

City: FLORA VISTA State: NM Zip: 87415

**Status Summary:**☐ THIS IS A FOLLOW UP INSPECTION☒ FOLLOW UP INSPECTION REQUIRED☐ NO FOLLOW UP INSPECTION REQUIRED**Findings:**

1 Number of Comments

0 Number of Corrective Actions

☐ Corrective Action Response Requested**ANY CORRECTIVE ACTION(S) FROM  
PREVIOUS INSPECTIONS THAT HAVE NOT  
BEEN ADDRESSED ARE STILL APPLICABLE****Contact Information:**

Contact Name	Phone	Email	Comment
Labowskie, Steve		steve.labowskie@state.co.us	
Chollett, Shannon		shannon.chollett@state.co.us	
Andrews, Dave		david.andrews@state.co.us	

**Inspected Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
214628	WELL	SI	03/01/1993	GW	067-06232	ESTER (OWP) 1	SI

**General Comment:**

January 21, 2020 Tuesday

RU pump, pumped 10 bbls water, no returns, RU to mix cement, Mix and pump 25 sks type 2 cement, Displace with 11 bbls water, Well circulated after starting displacement. POOH with tbq, laid down setting tool. PU and RIH with a CIBP on tbq and set at 2550'. Land EOT at 2547'. Mix and pump 10 sks type 2 cement, Displace with 9.5 bbls water. POOH with tbq, land down setting tool. RU RMWS, RIH with CBL tools, pulled CBL from 2350' to surface. Cement top at 2100'. (unable to determine the present of 7" casing behind 4-1/2" casing from log.) Bled off Braden Head, Cut a 1-1/2" by 3" hole in orange peel of 9-5/8" casing, lowered a light in about 3' and took pictures, no 7" casing visible. Lowered a tag line into surface pipe and tagged at about 50'. Welded a patch over the hole in orange peel. RIH with tbq to 2200'. RU pump, broke circulation, mix and pump 15 sks type 2 cement and displaced with 7.5 bbls water. POOH with tbq. SWI, sdfn.

**Inspected Facilities**Facility ID: 214628 Type: WELL API Number: 067-06232 Status: SI Insp. Status: SI**Attached Documents**You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
402304366	INSPECTION PHOTOS	<a href="http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=5057901">http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=5057901</a>