



RECEIVED
AUG 20 1962

RECEIVED
AUG - 8 1962

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO
OIL & GAS
CONSERVATION COMMISSION

OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME State Peterson WELL NO. 1

FIELD Tow Creek WILDCAT _____ COUNTY Routt

LOCATION NE SW Section 18 Township 6N Range 86W Meridian 6th PM
(Quarter Quarter)

2349 feet from S Section Line and 3059.3 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

We propose to abandon this well as it is uneconomical to produce. Approximately 2400' of 5 1/2" casing will be pulled, the well will be plugged, and a marker will be set as per OGCC regulations.

We plan to pull rods and tubing, set a 10 sack cement plug at 2500 ft using the pump and plug method. Cut and pull approximately 2400 ft. of 5 1/2" casing. Fill hole with mud laden fluid and set a 10 sack cement plug and marker at the surface.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: _____
 Date AUG 20 1962
 Director [Signature]
 JNH-ARB
 OGCC (3) GRW HSMcM

Company TEXACO Inc. Date 8-4-62
 Address Box 157, Craig, Colo. Phone No. 824-6565
 By [Signature] Title _____
 (Signature)
 H. S. McMinn, District Superintendent