




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



107-05986

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompletion

☐

✓ Notice of Intention to Abandon Well

☒

Other

☐

(Check appropriate space)

LEASE NAME Quaintance Hocking WELL NO. 9
FIELD Tow Creek WILDCAT COUNTY Routt
LOCATION NE SE Section 18 Township 6N Range 86W Meridian 6th PM
(Quarter Quarter)
1634 feet from S Section Line and 1020 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

We propose to abandon this well as it is uneconomical to produce. We plan to pull rods and tubing. Cut and pull 2200 ft. of 5 1/2" casing. A 10 sack cement plug will be set in 5 1/2" casing at 2500 ft. A 10 sack cement plug will be set in 8 5/8" casing at surface. Set marker at surface as per OGCC regulations.

The casing record on this well is as follows:

39 ft. of 13" 50# cemented to surface.
822 ft. of 8 5/8" 24# cemented with 260 sacks.
2641 ft. of 5 1/2" 14# cemented with 50 sacks.

DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	



I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

SEP 11 1962

Date

Director

JNH-ARB

OGCC (3) HSMcM

Company TEXACO Inc.

Date 9-6-62

Address Box 157, Craig, Colo.

Phone No. 824-6565

By H. S. McMinn

(Signature)

Title

H. S. McMinn, District Superintendent