

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402301143

Receive Date:

02/03/2020

Report taken by:

Candice (Nikki) Graber

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATION

Name of Operator: <u>PDC ENERGY INC</u>	Operator No: <u>69175</u>	Phone Numbers
Address: <u>1775 SHERMAN STREET - STE 3000</u>		Phone: <u>(303) 860-5800</u>
City: <u>DENVER</u>	State: <u>CO</u>	Zip: <u>80203</u>
Contact Person: <u>Karen Olson</u>	Email: <u>COGCCSpillRemediation@pdce.com</u>	Mobile: <u>()</u>

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 14468 Initial Form 27 Document #: 402215364

PURPOSE INFORMATION

- | | |
|--|--|
| <input type="checkbox"/> 901.e. Sensitive Area Determination | <input checked="" type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water |
| <input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste | <input type="checkbox"/> Rule 906.c.: Director request |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input type="checkbox"/> Other _____ |

SITE INFORMATION

N Multiple Facilities (in accordance with Rule 909.c.)

Facility Type: <u>LOCATION</u>	Facility ID: <u>333281</u>	API #: _____	County Name: <u>WELD</u>
Facility Name: <u>Cozzens Multi-Well D</u>		Latitude: <u>40.505260</u>	Longitude: <u>-104.663780</u>
		** correct Lat/Long if needed: Latitude: <u>40.495601</u>	Longitude: <u>-104.669672</u>
QtrQtr: <u>NWNE</u>	Sec: <u>9</u>	Twp: <u>6N</u>	Range: <u>65W</u>
		Meridian: <u>6</u>	Sensitive Area? <u>Yes</u>

SITE CONDITIONS

General soil type - USCS Classifications SM Most Sensitive Adjacent Land Use Residential

Is domestic water well within 1/4 mile? No Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

An occupied building is located 268 feet and wetlands are located 181 feet from location.

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- ☒ E&P Waste ☐ Other E&P Waste ☐ Non-E&P Waste
- ☒ Produced Water ☐ Workover Fluids
- ☐ Oil ☐ Tank Bottoms
- ☐ Condensate ☐ Pigging Waste
- ☐ Drilling Fluids ☐ Rig Wash
- ☐ Drill Cuttings ☐ Spent Filters
- ☐ Pit Bottoms
- ☐ Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	Refer to Figure 1 and Table 2	Excavation Groundwater Sampling
Yes	SOILS	Refer to Figure 1 and Table 1	Excavation and Confirmation Soil Sampling

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

On October 7, 2019, historic hydrocarbon impacts were discovered during routine produced water vessel maintenance. Excavation activities were initiated and approximately 490 cubic yards of impacted material were removed and transported to the North Weld Waste Management Facility for disposal.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Sixteen soil samples (SS01 – SS16) were collected from the unsaturated and saturated intervals of the excavation extent at 13 feet, 15 feet, and 16 feet below ground surface (bgs). Soil samples were submitted to Summit Scientific Laboratory for analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene, total petroleum hydrocarbons (TPH) – gasoline range organics (GRO) by EPA Method 8260B, and TPH– diesel range organics (DRO) by EPA Method 8015. Analytical results indicated that constituent concentrations were below COGCC Table 910-1 standards in the soil samples collected from the final excavation extent. The excavation extent and soil samples locations are illustrated on Figure 1. Soil analytical data is summarized in Table 1.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

On October 16, 2019, one groundwater sample (GW01) was collected from the excavation area and submitted to Summit Scientific Laboratory for analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX) by EPA Method 8260B. Analytical results indicated that the benzene concentration was in exceedance of the COGCC Table 910-1 standard. The groundwater sample location is illustrated on Figure 1 and analytical data is summarized in Table 2.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☒ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

A groundwater assessment will be conducted to delineate the extent of remaining dissolved-phase hydrocarbon impacts.

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 16

Number of soil samples exceeding 910-1 1

Was the areal and vertical extent of soil contamination delineated? Yes

Approximate areal extent (square feet) 1750

NA / ND

-- Highest concentration of TPH (mg/kg) 860

NA Highest concentration of SAR

BTEX > 910-1 Yes

Vertical Extent > 910-1 (in feet) 16

Groundwater

Number of groundwater samples collected 1

Was extent of groundwater contaminated delineated? No

Depth to groundwater (below ground surface, in feet) 15

Number of groundwater monitoring wells installed 0

Number of groundwater samples exceeding 910-1 1

-- Highest concentration of Benzene (µg/l) 92

-- Highest concentration of Toluene (µg/l) 170

-- Highest concentration of Ethylbenzene (µg/l) 31

-- Highest concentration of Xylene (µg/l) 530

NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 910-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☒ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) 490

Volume of liquid waste (barrels) 50

☒ Is further site investigation required?

Seven monitoring wells will be installed within and surrounding the former excavation area to delineate the extent of remaining dissolved-phase hydrocarbon impacts. Proposed monitoring locations are illustrated on Figure 2.

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No _____

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Between October 7 and October 15, 2019, approximately 490 cubic yards of impacted material were removed and transported to the North Weld Waste Management Facility for disposal.

REMEDICATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Seven monitoring wells (BH01 - BH07) were installed on December 3 and December 10, 2019, within and surrounding the former excavation area. Boring and well completion logs are included in the attached groundwater monitoring report. Monitored natural attenuation (MNA) was selected as the remediation strategy for this site during the fourth quarter 2019 and will remain the selected remediation strategy for the first quarter 2020.

Soil Remediation Summary

☐ In Situ

_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Air sparge / Soil vapor extraction
_____ Natural Attenuation
_____ Other _____

☒ Ex Situ

Yes _____ Excavate and offsite disposal
If Yes: Estimated Volume (Cubic Yards) _____ 490
Name of Licensed Disposal Facility or COGCC Facility ID # _____
_____ Excavate and onsite remediation
_____ Land Treatment
_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Other _____

Groundwater Remediation Summary

☐ Bioremediation (or enhanced bioremediation)
☐ Chemical oxidation
☐ Air sparge / Soil vapor extraction
☐ Natural Attenuation
☐ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

PDC will conduct quarterly groundwater monitoring at the seven monitoring wells (BH01 - BH07) until closure criteria are achieved.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: ☒ Quarterly ☐ Semi-Annually ☐ Annually ☐ Other _____

Report Type: ☒ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report

☐ Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes _____

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use.

Volume of E&P Waste (solid) in cubic yards _____ 490

E&P waste (solid) description _____ E&P contaminated soil

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: North Weld Waste Management Facility

Volume of E&P Waste (liquid) in barrels _____ 50

E&P waste (liquid) description _____ Impacted groundwater

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: NGL Energy Disposal Facility

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No _____

Do all soils meet Table 910-1 standards? _____

Does the previous reply indicate consideration of background concentrations? _____

Are the only residual soil impacts pH, SAR, or EC at depths greater than 3 feet below ground surface? _____

Does Groundwater meet Table 910-1 standards? _____

Is additional groundwater monitoring to be conducted? _____

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The excavation area was backfilled and compacted to match pre-existing conditions. The tank battery was reconstructed and remains operational.

Is the described reclamation complete? _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim? ☐ Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. _____

Actual Spill or Release date, if known. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 10/07/2019

Date of commencement of Site Investigation. 10/07/2019

Date of completion of Site Investigation. _____

REMEDIAL ACTION DATES

Date of commencement of Remediation. 10/07/2019

Date of completion of Remediation. _____

SITE RECLAMATION DATES

Date of commencement of Reclamation. _____

Date of completion of Reclamation. _____

OPERATOR COMMENT

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Karen Olson

Title: Senior Program Manager

Submit Date: 02/03/2020

Email: COGCCSpillRemediation@pdce.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Candice (Nikki) Graber

Date: 02/10/2020

Remediation Project Number: 14468

COA Type

Description

--	--

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num

Name

402301143	FORM 27-SUPPLEMENTAL-SUBMITTED
402301149	MONITORING REPORT

Total Attach: 2 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)