



**RECEIVED**  
JUL 21 1958  
(SUBMIT IN TRIPLICATA)  
OIL & GAS  
CONSERVATION  
**UNITED STATES**  
**DEPARTMENT OF THE INTERIOR**  
**GEOLOGICAL SURVEY**



Land Office Denver  
Lease No. Colo.-05556  
Unit U.S.A. Morris

**RECEIVED**  
JUL 18 1958  
DIVISION  
Leasing Branch  
**GEOLOGICAL SURVEY**  
Colorado

## SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL.....	SUBSEQUENT REPORT OF WATER SHUT-OFF.....
NOTICE OF INTENTION TO CHANGE PLANS.....	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING.....
NOTICE OF INTENTION TO TEST WATER SHUT-OFF.....	SUBSEQUENT REPORT OF ALTERING CASING.....
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL.....	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR.....
NOTICE OF INTENTION TO SHOOT OR ACIDIZE.....	SUBSEQUENT REPORT OF ABANDONMENT.....
NOTICE OF INTENTION TO PULL OR ALTER CASING.....	SUPPLEMENTARY WELL HISTORY.....
NOTICE OF INTENTION TO ABANDON WELL.....	Rep. of Spud, Run & Cst. <span style="float: right;">X</span>

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

July 16, 1958

Well No. 1 is located 1955 ft. from N line and 660 ft. from E line of sec. 14  
(1/4 Sec. and Sec. No.)      6N      79W      6th P.M.  
(Twp.)      (Range)      (Meridian)  
Rand-Waldon Area      Jackson      Colorado  
(Field)      (County or Subdivision)      (State or Territory)

The elevation of the derrick floor above sea level is \_\_\_\_\_ ft. Not determined

### DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

7-12-58 - Spudded 9" hole at 9:30 AM

Approved 7/18/58  
A. G. Frazier  
District Engineer

7-13-58 - Ran 22 fts. 10-3/4" OD 32.75#, 40.5#, 45.5# BKT NHO J55 R3 Sals. ST&C Casing set at 631' with Lardin float shoe on bottom & Lardin Cents, 55# & 619'. Cst. casing by Rocky Mountain Cementers with 490 sx 15# ideal reg. bulk cnt. w/2% Calc. Chloride. Started pumping cnt. at 10:10 PM. Plug down at 11 PM. Cst. circ. Had returns of approx. 10 bbls. Max. pump press. 450#.

7-14-58 Tested 10-3/4" casing with 500# - Held OK

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Amerada Petroleum Corporation

Address Box 1250 -  
Casper, Wyoming

By A. G. Stewart  
Title Dist. Supt.

AJJ	
DVR	
WRS	
FLM	
IAM	
FJP	✓
HP	✓