



99999999

JL 28 1958

050575008

Calo.
O & H Comm.Budget Bureau No. 42-R358.4
Approval expires 12-31-60.

(SUBMIT IN TRIPLICATE)
OIL & GAS
CONSERVATION COMMISSION UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Land Office Denver
Lease No. Colo. -05556
Unit U.S.A. Morris

SUNDRY NOTICES AND REPORTS ON WELLS

AJJ	
DVR	
WRS	
HHM	
JAM	
FJD	
JJD	
FILE	

NOTICE OF INTENTION TO DRILL	SUBSEQUENT REPORT OF WATER SHUT-OFF
NOTICE OF INTENTION TO CHANGE PLANS	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING
NOTICE OF INTENTION TO TEST WATER SHUT-OFF	SUBSEQUENT REPORT OF ALTERING CASING
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR
NOTICE OF INTENTION TO SHOOT OR ACIDIZE	SUBSEQUENT REPORT OF ABANDONMENT
NOTICE OF INTENTION TO PULL OR ALTER CASING	SUPPLEMENTARY WELL HISTORY
NOTICE OF INTENTION TO ABANDON WELL	Report of DST #1 & DST #2

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

Well No. 1 *Morris* is located 1955 ft. from [S] line and 660 ft. from [E] line of sec. 14
NE/4, SE/4, Sec. 14 6N 79W 6th P.M.
 (1/4 Sec. and Sec. No.) (Twp.) (Range) (Meridian)
Hand-Maldon Area Jackson Colorado
 (Field) (County or Subdivision) (State or Territory)

The elevation of the derrick floor above sea level is 8514' ft. Ord.
8552' D.P.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

7-20-58

DST No. 1 by Johnston Testers Double Packer, 1 hr. test from 2535-2634', 4-1/2" D.P., 3/4" bottom opening & 1" top opening. Opened tool at 3:06 AM, air lined, good blow for 25 mins. & decreased to very weak blow at end of test. Closed tool at 4:06 AM for 1/2 hr. BHP. Rec. 225' fresh muddy water. No show oil or gas. IHP 100%, IFP 10%, FFP 105%, FHP 1005, 1/2 hr. BHP 10 mins. 500#, 20 mins. 875#, 30 mins. 960#.

7-21-58

DST No. 2 by Johnston Testers from 2736-2748', Basal Coalmont Form., 1 hr. test, 4-1/2" D.P., 3/4" opening in tool. Opened tool at 7:15 AM. Weak blow of air lined. for 7 mins. & died. Dead 20 mins. Closed & reopened tool at 7:51 AM. Weak blow for 4 mins. & died. Dead 29 mins. Closed tool at 8:15 AM for 30 mins. BHP. Rec. 60' drlg. mud w/very light rainbow of oil in mud. No show gas or water. IHP 1310%, IFP 13, FFP 25, 1/2 hr. BHP 60, FHP 1300#.

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Amerada Petroleum CorporationAddress Box 1250Casper, Wyoming

00208474

By W. Stewart
 Title District Supt.