




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐

Notice of Intention to Change Plans ☐

Notice of Intention to Abandon Well ☐

Report of Remedial Work ☐

Report of Recompletion ☐

Other ☒

(Check appropriate space)

LEASE NAME U.S.A. - Thompson

WELL NO. 1

FIELD Walden Area

WILDCAT Wildcat COUNTY Jackson

LOCATION NE/4, SE/4 Section 8

Township 6N Range 79W Meridian 6th PM

1980 feet from S Section Line and 660 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

8-25-61

DST #1 - By Johnston Tester. 2 hour test from 1623-1685', Top of sand 1627', 4-1/2" D.P., 5/8" opening in tool, opened tool at 4:30 AM. Weak blow of air for 1-1/2 hrs., decreasing to a very weak blow at end of test. Shut in at 6:30 AM for 1-1/2 hr. BHP. Recovered 220' very slightly gas cut drilling mud. No show of oil or water. IHP - 199, IFP - 67, FFP - 128 FHP - 769, 1-1/2 Hr. S.I. Press. at 10 min. intervals - 10 min. 647#, 20 min. 677#, S.I. Press. remained at 677# for remainder of shut in period.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

AUG 30 1961

Date Aug 30 1961
Director A. J. Gersin

Company Amerada Petroleum Corp. Date August 29, 1961

Address Box 1250, Casper, Wyoming Phone No. 237-9351

By D. C. Malt Title District Supt.
(Signature)