

**FORM  
5**Rev  
02/20**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402345710

Date Received:

**DRILLING COMPLETION REPORT**

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 96850

Contact Name: Jeff Kirkland

Name of Operator: TEP ROCKY MOUNTAIN LLC

Phone: (970) 263-2736

Address: PO BOX 370

Fax:

City: PARACHUTE State: CO Zip: 81635

Email: jkirkland@terraep.com

API Number 05-045-24277-00

County: GARFIELD

Well Name: FEDERAL

Well Number: RWF 43-11

Location: QtrQtr: LOT 5 Section: 12 Township: 6S Range: 94W Meridian: 6  
FNL/FSL FEL/FWL

Footage at surface: Distance: 2021 feet Direction: FNL Distance: 1258 feet Direction: FWL

As Drilled Latitude: 39.542007 As Drilled Longitude: -107.841629

GPS Data: GPS Quality Value: 3.2 Type of GPS Quality Value: PDOP Date of Measurement: 11/07/2019

GPS Instrument Operator's Name: W. Kirkpatrick

FNL/FSL

FEL/FWL

\*\* If directional footage at Top of Prod. Zone Dist: 2489 feet Direction: FSL Dist: 772 feet Direction: FEL  
Sec: 11 Twp: 6S Rng: 94W

FNL/FSL

FEL/FWL

\*\* If directional footage at Bottom Hole Dist: 2406 feet Direction: FSL Dist: 933 feet Direction: FEL  
Sec: 11 Twp: 6S Rng: 94W

Field Name: RULISON

Field Number: 75400

Federal, Indian or State Lease Number: COC027822

Spud Date: (when the 1st bit hit the dirt) 12/15/2019 Date TD: 12/20/2019 Date Casing Set or D&amp;A: 12/21/2019

Rig Release Date: 03/03/2020 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9169 TVD\*\* 8648 Plug Back Total Depth MD 9127 TVD\*\* 8606

Elevations GR 5467 KB 5491

Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

CBL, NEU, (DEN/NEU in 045-24269)

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	47.44	0	84	140	0	84	VISU
SURF	13+1/2	9+5/8	36	0	1,042	275	0	1,042	CBL
1ST	8+3/4	4+1/2	11.6	0	9,159	1,250	1,651	9,159	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,417				
WASATCH	4,563				
OHIO CREEK	4,971				
WILLIAMS FORK	5,268				
CAMEO	8,232				
ROLLINS	9,056				

Operator Comments:

The GPS "as drilled" coordinates and dates of measurement is actual data of the existing well conductor location prior to the spud date.

No MUD logs were run on this well.

Alternative Logging Program: No open hole logs were run. Density Neutron log was run on RWF 432-11 (API 045-24269).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Ashely NoonanTitle: Sr. Regulatory Analyst

Date: \_\_\_\_\_

Email: anoonan@terraep.com

### Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
402345726	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
402346742	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
402345723	LAS-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402345724	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402345725	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402346743	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402346744	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

