

FORM
5ARev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402317308

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10110
 2. Name of Operator: GREAT WESTERN OPERATING COMPANY LLC
 3. Address: 1001 17TH STREET #2000
 City: DENVER State: CO Zip: 80202
 4. Contact Name: Eileen Roberts
 Phone: (720) 595-2115
 Fax:
 Email: eroberts@gwp.com

5. API Number 05-123-46413-00
 6. County: WELD
 7. Well Name: Schneider HD
 Well Number: 11-019HNX
 8. Location: QtrQtr: NWSW Section: 7 Township: 4N Range: 66W Meridian: 6
 9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 12/29/2019 End Date: 01/12/2020 Date of First Production this formation: 02/04/2020

Perforations Top: 8343 Bottom: 17855 No. Holes: 1664 Hole size: 38/100

Provide a brief summary of the formation treatment:

Open Hole: ☐

2,893 bbls 15% HCL Acid; 780,705# 100 Mesh Sand; 8,780,260 # 20/40 Sand; 224,051 bbls Gelled Fluid; Flowback determined from well test separator

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 226944

Max pressure during treatment (psi): 4832

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.33

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.98

Total acid used in treatment (bbl): 2893

Number of staged intervals: 64

Recycled water used in treatment (bbl):

Flowback volume recovered (bbl): 28655

Fresh water used in treatment (bbl): 224051

Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 9560965

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 02/07/2020 Hours: 24 Bbl oil: 268 Mcf Gas: 1969 Bbl H2O: 1083

Calculated 24 hour rate: Bbl oil: 268 Mcf Gas: 1969 Bbl H2O: 1083 GOR: 7347

Test Method: Flowing Casing PSI: 2960 Tubing PSI: 2379 Choke Size: 18/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1281 API Gravity Oil: 53

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7912 Tbg setting date: 01/21/2020 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

The bottom of the completed interval is at 80' FNL and 523' FWL of Section 11.
During stimulation the wellbore was isolated by a composite bridge plug set at 17873'.
Great Western certifies that none of the wellbore beyond the unit boundary setback was completed.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts
Title: Regulatory Analyst Date: _____ Email: eroberts@gwp.com
:

Attachment Check List

Att Doc Num Name

--	--

Total Attach: 0 Files

General Comments

User Group Comment Comment Date

		Stamp Upon Approval
--	--	------------------------

Total: 0 comment(s)