

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
401811295

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:
02/12/2019

Well Name: Rampart Well Number: A33-750
Name of Operator: NOBLE ENERGY INC COGCC Operator Number: 100322
Address: 1001 NOBLE ENERGY WAY
City: HOUSTON State: TX Zip: 77070
Contact Name: Craig Richardson Phone: (303)228-4232 Fax: ()
Email: regulatorynotification@nblenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030009

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 21 Twp: 6N Rng: 64W Meridian: 6

Latitude: 40.466040

Longitude: -104.561000

Footage at Surface: 652 Feet FNL/FSL FSL 1005 Feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4727

County: WELD

GPS Data: GPS Quality Value: 1.6 Type of GPS Quality Value: PDOP Date of Measurement: 03/21/2018

Instrument Operator's Name: Casey Kohout

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FSL 460 FNL 2640 FWL 460 FSL 2634 FEL
Sec: 28 Twp: 6N Rng: 64W Sec: 33 Twp: 6N Rng: 64W

LOCAL GOVERNMENT INFORMATION

County: WELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below.

☒ Yes ☐ No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☒

The local government siting permit type is: WOGLA (Non-1041)

The local government siting permit was filed on: 04/24/2019

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

WOGLA was approved 5/21/2019 - Permit# WOGLA 19-0063

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T6N-R64W, 6th P.M., Sec 29: N/2NE/4

The completed portion of the wellbore does not penetrate the described lease but the lease is within the unit.

Total Acres in Described Lease: 80 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 658 Feet

Building Unit: 679 Feet

High Occupancy Building Unit: 3089 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 647 Feet

Above Ground Utility: 634 Feet

Railroad: 5280 Feet

Property Line: 469 Feet

School Facility: 5280 Feet

School Property Line: 5280 Feet

Child Care Center: 3089 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 05/15/2018

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 635 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Proposed Drilling and Spacing Unit configuration, Docket No. 180700557, scheduled for October 2018 COGCC Hearing, consisting of: T6N-R64W, 6th P.M., Sec 28: W2, W2E2; Sec 29: All; Sec 32: All; Sec 33: W2, W2E2

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: _____

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-2909	2240	Sec. 28, 29, 32 & 33

DRILLING PROGRAM

Proposed Total Measured Depth: 17094 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 227 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Drilling waste disposal information added in Waste Management Plan to address non-oil based mud and fluids used in non-producing portion of wellbore.

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42	0	80	144	80	0
SURF	13+1/2	9+5/8	36	0	1850	658	1850	0
1ST	8+1/2	5+1/2	17	0	17094	1886	17094	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments Noble respectfully submits this application for a permit to drill, which is a part of a thirteen well pad producing to pad A21 Tank.

Nearest well in the same formation is the RAMPART A33-740, the distance was calculated using 2D data.

The nearest well belonging to another operator is Noffsinger 31-33, PR, 05-123-14260, operated by PDC Energy - 69175. Distance was calculated in 3D. 317.S consent is not required.

The Exception Location and Twinning Waiver language is included in the attached SUA, (Page 5, Section 6).

Noble Energy shall isolate both the Fox Hills and Upper Pierre Aquifers with surface casing from hydrocarbon bearing zones and exposures to oil based drilling fluid. Noble Energy also agrees to not expose the Upper Pierre Aquifer to oil based mud.

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: 449369

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Webb

Title: Sr. Regulatory Analyst Date: 2/12/2019 Email: Julie.webb@nblenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: 4/8/2020

Expiration Date: 04/07/2022

API NUMBER

05 123 50927 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type	Description
Drilling/Completion Operations	<p>Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test:</p> <ol style="list-style-type: none"> 1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation. 2) If a delayed completion, 6 months after rig release and prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation. 3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.
Drilling/Completion Operations	<ol style="list-style-type: none"> 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (Spud Notice), for the first well/activity on the pad and provide 48 hour spud notice for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j and provide cement coverage from the end of production casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Oil-based drilling fluid is to be used only after all aquifers are covered.
Drilling/Completion Operations	<p>Operator acknowledges the proximity of the listed non-producing well(s). Operator agrees to provide mitigation Option 3 (per the DJ Basin Horizontal Offset Policy, ensure all applicable documentation is submitted , and submit Form 42(s) "OFFSET MITIGATION COMPLETED" for the remediated well(s), referencing the API Number of the proposed horizontal wells stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of the proposed wells.</p> <p>Achziger 14-33 (API NO 123-12466)Bauer 2 (API NO 123-12800)</p>
Drilling/Completion Operations	<p>Operator acknowledges the proximity of the following non-operated listed wells: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>Danley 12-28 (API NO 123-19473)Noffsinger 11-33 (API NO 123-14258) Danley 14-28 (API NO 123-19044)Noffsinger 12-33 (API NO 123-19356) Danley 13-28 (API NO 123-19580)Wells 24-21 (API NO 123-20034) Noffsinger 22-33 (API NO 123-20237)Noffsinger 32-33 (API NO 123-20739) Dewey 22-28 (API NO 123-20155)French 41-4 (API NO 123-21788)</p>
Drilling/Completion Operations	<p>Operator acknowledges the proximity of the listed wells: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>Achziger 11-33 (API NO 123-12464)Webster 15-28 (API NO 123-12690) French 9-33 (API NO 123-12941)Webster 9-28 (API NO 123-13060) Sitzman 13-33 (API NO 123-13567)Wardlaw 16-28 (API NO 123-21812) Rohr A 28-25 (API NO 123-32718)</p>
Drilling/Completion Operations	<p>This Permit to Drill is approved subject to all the BMPs and COAs on the most recently approved Form 2A and any subsequently approved Form 4 for the Oil and Gas Location. The most recently approved Form 2A and any subsequent Form 4s containing applicable COAs for this location shall be posted onsite during construction, drilling, and completions operations.</p>

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Bradenhead Monitoring: Noble Energy acknowledges and will comply with COGCC Policy for Braden-head Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
2	Drilling/Completion Operations	If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations.
3	Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on the pad will be logged with open-hole resistivity log and gamma-ray log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.
4	Drilling/Completion Operations	Noble Energy will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.

Total: 4 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.
http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

Attachment Check List

Att Doc Num	Name
401811295	FORM 2 SUBMITTED
401839533	DIRECTIONAL DATA
401839534	DEVIATED DRILLING PLAN
401839535	SURFACE AGRMT/SURETY
401845764	WELL LOCATION PLAT
401861550	OffsetWellEvaluations Data
401937473	EXCEPTION LOC REQUEST
402364759	OFFSET WELL EVALUATION

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	04/07/2020
Engineer	Offset Wells Evaluated	04/03/2020
Permit	COGCC conducted the technical review for the related Oil and Gas Location Assessment permit, Form 2A document # 401811253 under the statutory authority provided through SB 19-181, including the Objective Criteria. The Director approved the Form 2A on 3/9/2020, amending Location ID # 449369 subject to conditions included in the permit. The well proposed by this related Form 2 was contemplated during COGCC's review of the Form 2A. The Objective Criteria Review Memo (Doc# 2479222) can be found in the document file for this Location.	03/23/2020
Permit	<ul style="list-style-type: none"> •Received concurrence on the removal of the surface related BMPs and updating of the open hole logging BMP. •Received concurrence on the addition of the unit configuration and spacing order number. •COGCC Staff has added the Local Government siting permit information and the School and Childcare Center distances provided by the operator. •Initial permitting review complete. 	12/19/2019
Permit	<ul style="list-style-type: none"> •Requested approved WOGLA Permit# for the Well Location tab. •Removed the surface related BMPs and updated the open hole logging BMP. Requesting concurrence. •Requested school/child care distances for the Cultural Setbacks tab. •Added approved spacing order number and unit configuration. Requesting concurrence 	12/17/2019
Permit	Passed completeness.	02/13/2019

Total: 6 comment(s)