



|   |               |   |   |                         |              |
|---|---------------|---|---|-------------------------|--------------|
| <b>COMPANY</b><br>Public Service Company Of Colorado  |               |   |   | <b>DATE</b><br>4/7/2020 |              |
| <b>LEASE</b><br>Asbury Storage Unit-Fed #4. API# 05-077-05093 / BLM Lease # 14-08-001-86-02 |               |   |   |                         |              |
| <b>Surface Casing</b>   | <b>Weight</b> | <b>Grade</b>                              | <b>Thread</b>   | <b>Depth</b>            |              |
| 8-5/8"  | 24#           | J-55                                      | LT&C  | 539'                    |              |
| <b>Prod Casing</b>  | <b>Weight</b> | <b>Grade</b>                              | <b>Thread</b>   | <b>Depth</b>            |              |
| 4-1/2"  | 9.5#          | J-55                                      | LT&C  | 2777'                   |              |
| <b>Tubing String</b>  | <b>Size</b>   | <b>Weight</b>                             | <b>Grade</b>  | <b>Thread</b>           | <b>Depth</b> |
|   | 2 3/8         | 4.7#                                      | J-55  | 8rd EUE                 | 2678'        |
| <b>Second String</b>  | <b>Size</b>   | <b>Weight</b>                             | <b>Grade</b>  | <b>Thread</b>           | <b>Depth</b> |
|   |               |   |   |                         |              |
| <b>Prepared for:</b>  |               |   | <b>Perforations:</b><br>Dakota Open hole Section 2772' to 2810' |                         |              |
| <b>ITEM No#</b>   | <b>Length</b> | <b>Description</b>                        | <b>ID</b>   | <b>OD</b>               | <b>Depth</b> |
| 1   |               | 375 sks of surface cement from 539' - 0'  |   |                         |              |
| 2   |               | 12-1/4" surface hole                      | 12.25   |                         |              |
| 3   |               | 8-5/8" Surface Casing @ 539'              | 7.972   | 8.625                   | 539.00       |
| 4   |               | Hole size 6-3/4" drilled in October 1965  | 6.75  |                         |              |
| 5   |               | Estimated top of cement @ 757'. 135 sacks |   |                         | 757.00       |
| 6   |               | 2-3/8" production tubing landed at 2678'  | 1.901   | 2.375                   | 2678.00      |
| 7   |               | 2-3/8" x 4-1/2" Packer set @ 2678'        |   |                         |              |
| 8   |               | 4-1/2" Casing landed @ 2777'              | 3.965   | 4.5                     |              |
| 9   |               | Open Hole Section 2777' to 2810'          |   |                         | 7656.00      |
| <b>PREPARED BY</b><br>Jeff Schneider  |               |   | <b>PHONE:</b><br>970-381-9588                                   |                         |              |
| <b>OFFICE</b><br>Fort Morgan, CO  |               | <b>PHONE</b><br>970-867-9437              |   | <b>INVOICE #</b>        |              |