



COMPANY Public Service Company of Colorado				DATE 4/14/2020	
LEASE Storage Unit #33 API# 05-087-08006					
Surface Casing	Weight	Grade	Thread	Depth	
8-5/8"	24#	J-55	LT&C	317'	
Prod Casing	Weight	Grade	Thread	Depth	
5-1/2"	15.5#	K-55	LT&C	6550'	
Tubing String	Size	Weight	Grade	Thread	Depth
	2 7/8	6.5#	J-55	8rd EUE	6423'
Second String		Size	Weight	Grade	Thread
Prepared for:			Perforations: J Sand 6420' to 6428'		
ITEM No#	Length	Description	ID	OD	Depth
1		285 sks of surface cement from 317' - 0'			
2		12-1/4" surface hole	12.25		
3		8-5/8" Surface Casing @ 317'	7.972	8.625	317.00
4		Hole size 7-7/8"	7.875		
		Cement top 4760' CBL dated 7/24/1990 W/250 sks 50/50 poz & 150 sks G.			
6		2-7/8" production tubing landed at 6415'	2.347	2.875	6514.00
		J Sand Perfs 6420' to 6428'			
8		5-1/2" Casing landed @ 6550'	4.825	5.5	6550.00
PREPARED BY Jeff Schneider			PHONE: 970-381-9588		
OFFICE Fort Morgan, CO			PHONE 970-867-9437		INVOICE #