

FORM

2

Rev  
02/20

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

401513672

## APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

07/02/2019

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER: \_\_\_\_\_Refiling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: FEDERAL

Well Number: PA 14-23

Name of Operator: TEP ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: PO BOX 370

City: PARACHUTE

State: CO

Zip: 81635

Contact Name: VICKI SCHOEBER

Phone: (970)263-2731

Fax: ( )

Email: vschoeber@terraep.com

## RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160057

## WELL LOCATION INFORMATION

QtrQtr: LOT 2 Sec: 26 Twp: 6S Rng: 95W Meridian: 6

Latitude: 39.500029

Longitude: -107.964150

Footage at Surface: 1138 Feet FNL/FSL FNL 2183 Feet FEL/FWL FEL

Field Name: PARACHUTE

Field Number: 67350

Ground Elevation: 5486

County: GARFIELD

GPS Data: GPS Quality Value: 2.6 Type of GPS Quality Value: PDOP

Date of Measurement: 06/11/2015

Instrument Operator's Name: J. KIRKPATRICK

If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL

1120

FSL

1022

FWL

1120

FSL

1022

FWL

Sec: 23

Twp: 6S

Rng: 95W

Sec: 23

Twp: 6S

Rng: 95W

## LOCAL GOVERNMENT INFORMATION

County: GARFIELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below.

☐ Yes ☒ NoIf yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☐

The local government siting permit type is: \_\_\_\_\_

The local government siting permit was filed on: \_\_\_\_\_

The disposition of the application filed with the local government is: \_\_\_\_\_

Additional explanation of local process:

TEP Rocky Mountain LLC has contacted Garfield County, the local government with jurisdiction over the siting of this proposed oil and gas location and determined that per the Garfield County Land Use and Development Code, Table 3-403, "Oil and Gas Drilling and Production" and "Hydraulic Fracturing, Remote Surface Location" are a use by right or Exempt from Land Use Regulation at this site. Garfield County's disposition is not required for the purposes of this submittal.

## LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T6S-R95W:

Section 13: Lots 1-4, E2, E2W2

Section 23: Lots 1-10, SENE, NESW, N2SE

Section 24: Lots 1-5, NE, NENW, S2NW, N2S2

Section 25: NWNE, N2NW, SWNW, NWSW

Section 26: Lots 1, 2, 7, 8, N2SE, SWSE

Total Acres in Described Lease: 2140 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC073094

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 936 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 4828 Feet

Building Unit: 4883 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 4604 Feet

Above Ground Utility: 4285 Feet

Railroad: 5079 Feet

Property Line: 2909 Feet

School Facility: 5280 Feet

School Property Line: 5280 Feet

Child Care Center: 5280 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 316 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary \_\_\_\_\_ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: \_\_\_\_\_

## OBJECTIVE FORMATIONS

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| WILLIAMS FORK          | WMFK           | 1-229                   |                               |                                      |

## DRILLING PROGRAM

Proposed Total Measured Depth: 9331 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: \_\_\_\_\_ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Drilling pit

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR   | 26           | 18             | 47.4  | 0             | 80            | 134       | 80      | 0       |
| SURF        | 13+1/2       | 9+5/8          | 36    | 0             | 1100          | 266       | 1100    | 0       |
| 1ST         | 8+3/4        | 4+1/2          | 11.6  | 0             | 9331          | 878       | 9331    |         |

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

A review of the Director's Objective Criteria regarding this location is attached.

Nearest permitted or completed well in same formation: Federal PA 314-23 (#401516704).

This application is in a Comprehensive Drilling Plan No CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: VICKI SCHOEBER

Title: REGULATORY SPECIALIST Date: 7/2/2019 Email: vschoeber@terraep.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).  
Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-101 and is hereby approved.

COGCC Approved: \_\_\_\_\_

Director of COGCC

Date: 4/23/2020

Expiration Date: 04/22/2022

**API NUMBER**

05 045 24301 00

### **Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**COA Type**

**Description**

|                                |   |
|--------------------------------|---|
| Drilling/Completion Operations | <p>1) Operator shall comply with the most current revision of the Northwest Notification Policy.</p> <p>2) Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1).</p> <p>3) Operator shall provide cement coverage from the production casing shoe (4+1/2" FIRST STRING) to 200' above the Wasatch G. Isolation is required for offset Wasatch G Sand production and injection. Verify production casing cement coverage with a cement bond log.</p> <p>4) The Operator shall monitor the bradenhead pressure of the proposed well and all offset wells under Operator's control which penetrate the stimulated formation and have a treated interval separation of 300 feet or less. Monitoring shall occur from 24 hours prior to stimulation and shall continue until 24 hours after stimulation is complete. Recording shall be at a frequency of at least once per 24 hours with the capability of recording the maximum pressure observed during each 24 hour period. Operator shall notify COGCC Engineering staff if bradenhead pressures increase by more than 200 psig.</p> |
|--------------------------------|---|

### **Best Management Practices**

**No BMP/COA Type**

**Description**

|                                  |   |
|----------------------------------|---|
| 1 Drilling/Completion Operations | Alternative Logging Program: One of the first wells drilled on this pad will be logged with an open-hole resistivity log with gamma-ray, from TD into the surface casing. All wells on the pad will have a cement bond log (CBL) with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs will state "Alternative Logging Program - No open-hole logs were run" and will clearly identify the type of log and the well (by API#) in which open-hole logs were run. |
|----------------------------------|---|

Total: 1 comment(s)

## **Applicable Policies and Notices to Operators**

Piceance Rulison Field - Notice to Operators.

<http://cogcc.state.co.us/documents/reg/Policies/NoticeToOp-20060623-2.pdf>

NW Colorado Notification Policy.

[http://cogcc.state.co.us/documents/reg/Policies/nw\\_notification\\_procedures.pdf](http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf)

Notice Concerning Operating Requirements for Wildlife Protection.

[http://cogcc.state.co.us/documents/reg/Policies/Wildlife\\_Notice.pdf](http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf)

## **Attachment Check List**

| <b><u>Att Doc Num</u></b> | <b><u>Name</u></b>     |
|---------------------------|------------------------|
| 401513672                 | FORM 2 SUBMITTED       |
| 402051850                 | CORRESPONDENCE         |
| 402057380                 | OTHER                  |
| 402057381                 | PROPOSED BMPS          |
| 402079412                 | WELL LOCATION PLAT     |
| 402087657                 | DEVIATED DRILLING PLAN |
| 402087668                 | DIRECTIONAL DATA       |
| 402094011                 | FED. DRILLING PERMIT   |

Total Attach: 8 Files

## **General Comments**

| <b><u>User Group</u></b> | <b><u>Comment</u></b>   | <b><u>Comment Date</u></b> |
|--------------------------|---|----------------------------|
| Permit                   | Final Review Completed.   | 04/23/2020                 |
| Permit                   | 04/21/2020 - The Objective Criteria Review Memo (Doc# 2109192) is attached to the Form 2A associated with this APD. Following additional analysis arising out of the Objective Criteria, the Director determined that this application meets the standard for the protection of public health, safety, welfare, the environment and wildlife resources set by SB 19-181.  | 04/23/2020                 |
| Permit                   | Changed the disposition of application from Waived to blank.<br>Passed Permitting review  | 01/16/2020                 |
| Engineer                 | Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile of this proposed surface hole location is 107'. Operator's proposed surface casing set at 1,100' will cover all current water wells within one mile of the surface hole location.<br><br>Offset Well Evaluation: Existing offset oil and gas wells within 1,500 feet of this wellbore meet standards. No mitigation required. | 07/18/2019                 |
| Permit                   | Added Surety Bond ID.<br>Passed Completeness.   | 07/08/2019                 |

Total: 5 comment(s)