

**FORM**  
**5**Rev  
02/20**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402351531

Date Received:

**DRILLING COMPLETION REPORT**

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10633

Contact Name: Logan Siple

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

Phone: (303) 579-2174

Address: 1801 CALIFORNIA STREET #2500

Fax:

City: DENVER State: CO Zip: 80202

Email: logan.siple@crestonepr.com

API Number 05-123-47990-00

County: WELD

Well Name: Lochbuie Land

Well Number: 2C-25H-D166

Location: QtrQtr: NWNW Section: 25 Township: 1N Range: 66W Meridian: 6  
FNL/FSL FEL/FWL

Footage at surface: Distance: 918 feet Direction: FNL Distance: 297 feet Direction: FWL

As Drilled Latitude: 40.027010 As Drilled Longitude: -104.733900

GPS Data: GPS Quality Value: 1.9 Type of GPS Quality Value: PDOP Date of Measurement: 02/22/2019

GPS Instrument Operator's Name: Brent Hill

FNL/FSL FEL/FWL

\*\* If directional footage at Top of Prod. Zone Dist: 329 feet Direction: FNL Dist: 460 feet Direction: FWL  
Sec: 25 Twp: 1N Rng: 66W\*\* If directional footage at Bottom Hole Dist: 346 feet Direction: FNL Dist: 465 feet Direction: FEL  
Sec: 25 Twp: 1N Rng: 66W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 01/02/2019 Date TD: 02/13/2020 Date Casing Set or D&amp;A: 02/14/2020

Rig Release Date: 02/23/2020 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11855 TVD\*\* 7341 Plug Back Total Depth MD 11826 TVD\*\* 7341

Elevations GR 5078 KB 5101

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

Surface CBL, MWD/LWD, CBL

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	42	0	121	78	0	121	VISU
SURF	13+1/2	9+5/8	40	0	2,373	998	0	2,373	CBL
1ST	8+1/2	5+1/2	20	0	11,839	1,404	2,272	11,855	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,786		NO	NO	
SHARON SPRINGS	7,304		NO	NO	
NIOBRARA	7,323		NO	NO	

Operator Comments:

TPZ footages are estimated; well is not completed. Estimated completion Q3 2020.

No Open Hole Logs Were Run on this well.

Open Hole Log was run on the Lochbuie Land 2J-25H-D166 well, 123-47992; per BMP on APD;

GPS locations were taken on surface casing.

Surface Cement Report and Surface CBL Attached to the Preliminary Form 5 Referenced in the Related Forms

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Lindsey Organ

Title: Regulatory Coordinator

Date: \_\_\_\_\_

Email: lindsey.organ@crestonepr.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
402380432	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
402380428	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402380421	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402380423	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402380425	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402380426	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402380427	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

