

FORM
6Rev
02/20

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402367227

Date Received:

04/24/2020

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 72400

Contact Name: Jeff Schneider

Name of Operator: PUBLIC SERVICE COMPANY OF COLORADO

Phone: (970) 867-9437

Address: 1123 W 3RD AVE

Fax:

City: DENVER State: CO Zip: 80223

Email: jeff@schneiderenergy.com

For "Intent" 24 hour notice required,

Name: Browning, Chuck

Tel: (970) 433-4139

COGCC contact:

Email: chuck.browning@state.co.us

Type of Well Abandonment Report: ☒ Notice of Intent to Abandon ☐ Subsequent Report of Abandonment

API Number 05-077-07335-00

Well Name: ASBURY STORAGE UNIT-FED

Well Number: 5

Location: QtrQtr: SENW Section: 14 Township: 9S Range: 101W Meridian: 6

County: MESA

Federal, Indian or State Lease Number:

Field Name: ASBURY CREEK

Field Number: 3200

Only Complete the Following Background Information for Intent to Abandon

Latitude: 39.276030 Longitude: -108.634030

GPS Data: GPS Quality Value: 0.1 Type of GPS Quality Value: PDOP Date of Measurement: 05/18/2006

GPS Instrument Operator's Name: Paul Kellogg

Reason for Abandonment: ☐ Dry ☐ Production Sub-economic ☐ Mechanical Problems☒ Other This is an observation well in a gas storage field that is no longerCasing to be pulled: ☐ Yes ☒ No Estimated Depth:Fish in Hole: ☐ Yes ☒ No If yes, explain details belowWellbore has Uncemented Casing leaks: ☐ Yes ☒ No If yes, explain details below

Details:

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
DAKOTA	2734	2787			

Total: 1 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	11+1/4	8+5/8	24	294	115	294	0	VISU
1ST	6+3/4	4+1/2	9.5	2,734	270	2,734	350	CALC

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth _____ with _____ sacks cmt on top. CIBP #2: Depth _____ with _____ sacks cmt on top.
CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 75 sks cmt from 2787 ft. to 2634 ft. Plug Type: OPEN HOLE Plug Tagged: ☒

Set 35 sks cmt from 50 ft. to 0 ft. Plug Type: CASING Plug Tagged: ☐

Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at 344 ft. with 50 sacks. Leave at least 100 ft. in casing 244 CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set _____ sacks half in. half out surface casing from _____ ft. to _____ ft. Plug Tagged: ☐

Set _____ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☒ Yes ☐ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. _____ inch casing Cut and Cap Date: _____
of _____

*Wireline Contractor: _____ *Cementing Contractor: _____

Type of Cement and Additives Used: _____

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☐ No

Technical Detail/Comments:

There is an open hole section in this well from 2734' to 2787'. The open hole section will be filled with cement and brought up 100' into the casing to 2634'. This plug will be tagged.

There is no CBL on file for this well. The plan is to pump a open hole plug, wait 4 hours and then tag the cement plug. If the plug top is at an exceptable depth the casing and plug will be pressure tested to 500 psi, after which we will TOOHP with the tubing. We are planning on running a CBL from the top of the cement plug to surface, we will email a copy of the CBL to the COGCC and BLM Engineers. We will not proceed with the plugging operations until we are given approval by both engineers. A copy of the CBL will be submitted with the final form 6.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jeff Schneider

Title: Consultant Date: 4/24/2020 Email: jeff@schneiderenergy.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Katz, Aaron Date: 4/27/2020

CONDITIONS OF APPROVAL, IF ANY: _____

Expiration Date: 10/26/2020

COA Type	Description
	<p>1)Provide 48 hour notice of plugging MIRU via electronic Form 42.</p> <p>2)The approved Form 6, Notice of Intent will be at the location during all phases of plugging operations.</p> <p>3)Operator shall implement measures to control venting and to ensure that vapors and odors from well plugging operations do not constitute a nuisance or hazard.</p> <p>4)Properly abandon flowlines as per Rule 1105. File electronic Form 42 once on location abandonment complete. Within 30 days of an operator completing abandonment requirements for an off-location flowline or crude oil transfer line the operator shall submit a Flowline Report, Form 44.</p> <p>5)Check bradenhead annulus pressure prior to MIRU. Perform a bradenhead test if bradenhead pressure is greater than 25 psi, submit results electronically on a Form 17, and contact COGCC area engineer. If a well has a bradenhead pressure greater than 25 PSI measured at the time of the test then a sample of both the production and bradenhead gas (if sufficient volume to analyze) shall be collected and submitted for laboratory analysis of the gas composition and stable isotopes. The compositional analysis should include hydrogen, argon, oxygen, carbon dioxide, nitrogen, methane (C1), ethane (C2), ethene, propane (nC3), isobutane (iC4), butane (nC4), isopentane (iC5), pentane (nC5), hexanes +, specific gravity and British Thermal Units (BTU).The stable isotope analysis should include delta DC1, delta 13C1, delta 13C2, delta 13C3, delta 13iC4, delta 13nC4, delta 13iC5 (if possible), delta 13nC5 (if possible), and delta 13C of CO2 (if possible). The analytical results shall be submitted to the COGCC via Form 43 (Analytical Sample Submittal Form). Gas sample containers should be filled in accordance with container manufacturer or laboratory recommendations; purging multiple container volumes may not be feasible due to limited gas volumes. If water is encountered in the bradenhead during testing then samples (if sufficient quantity to analyze) should be collected and submitted for the laboratory analysis of major anions (chloride, carbonate, bicarbonate, and sulfate), cations (sodium, potassium, calcium, and magnesium) total dissolved solids (TDS), BTEX, DRO, GRO, and dissolved gasses (RSK 175). If there is a limited amount of water available then anions, cations and BTEX should be given first priority. Data from bradenhead water samples shall be submitted to the COGCC via Form 43. Please refer to Appendix A of the COGCC Operator Instructions for Bradenhead Testing and Reporting for more information regarding testing and sampling protocol. The operator shall provide notice to Environmental Supervisor Alex Fischer at alex.fischer@state.co.us or 303-894-2100 X 5138 and COGCC Engineer Craig Burger at craig.burger@state.co.us or 970-319-4194, a minimum of 72 hours prior to conducting field operations. Bradenhead testing and sample collection (if applicable). If samples are collected, copies of all final laboratory analytical results shall be provided to the COGCC within three (3) months of collecting the samples.</p> <p>6)This well has federal minerals. Operator shall notify COGCC engineering staff of any plugging changes required by the BLM or unexpected conditions in the field as soon as feasible.</p>

Attachment Check List

Att Doc Num	Name
402367227	FORM 6 INTENT SUBMITTED
402367241	WELLBORE DIAGRAM
402367242	OTHER
402380441	WELLBORE DIAGRAM

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	RTD: The current wellbore diagram has different open hole interval than the proposed, neither of which match what is COGCC well file.	04/21/2020

Total: 1 comment(s)