

FORM
2

Rev
02/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402372347

(SUBMITTED)

Date Received:

04/21/2020

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____

Refilling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: DRAKE

Well Number: 3X-HC-11-07-67

Name of Operator: NICKEL ROAD OPERATING LLC

COGCC Operator Number: 10669

Address: 1600 STOUT STREET SUITE 1850

City: DENVER

State: CO

Zip: 80202

Contact Name: JENNIFER LIND

Phone: (303)406-1117

Fax: ()

Email: JENNIFER.LIND@NICKELROADOPERATING.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20200034

WELL LOCATION INFORMATION

QtrQtr: NWSE Sec: 12 Twp: 7N Rng: 67W Meridian: 6

Latitude: 40.588172

Longitude: -104.837553

Footage at Surface: 2418 Feet FNL/FSL FSL 1595 Feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 5089

County: WELD

GPS Data: GPS Quality Value: 1.2 Type of GPS Quality Value: PDOP Date of Measurement: 09/15/2017

Instrument Operator's Name: DAHLMAN

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL 460 FEL FNL 460 FWL
1920 FNL 460 FEL 1920 FNL 460 FWL
Sec: 12 Twp: 7N Rng: 67W Sec: 11 Twp: 7N Rng: 67W

LOCAL GOVERNMENT INFORMATION

County: WELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below.

☒ Yes ☐ No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☒

The local government siting permit type is: WOGLA 18-0003

The local government siting permit was filed on: 01/18/2018

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

WOGLA 18-0003 APPROVED 02/08/18

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T7N-R67W-SEC.12: W/2 SE/4

Total Acres in Described Lease: 80 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building:	<u>1910</u> Feet
Building Unit:	<u>2241</u> Feet
High Occupancy Building Unit:	<u>5280</u> Feet
Designated Outside Activity Area:	<u>5280</u> Feet
Public Road:	<u>1579</u> Feet
Above Ground Utility:	<u>1553</u> Feet
Railroad:	<u>5280</u> Feet
Property Line:	<u>225</u> Feet
School Facility:	<u>5280</u> Feet
School Property Line:	<u>5280</u> Feet
Child Care Center:	<u>5280</u> Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 300 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: _____

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-2267	1280	SEC. 11 & 12: ALL

DRILLING PROGRAM

Proposed Total Measured Depth: 17365 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 1220 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42	0	80	100	80	0
SURF	12+1/4	9+5/8	36	0	1530	400	1530	0
1ST	8+1/2	5+1/2	20	0	17365	2390	17365	1000

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments This location has been built and contains 3 producing wells. The following changes from the previously approved Form 2 are being made via this refile:

- Offset Well Evaluation: updated list of wells attached
- BMPs: Updated to reflect current requirements
- Casing / Cement Program: Cement top for First String (Production String) updated

No other changes to this Form 2 are proposed at this time. Attachments have not been provided except as identified above as no changes are proposed. Note, this is an approved 318A.a. (GWA Window) exception location - see SUA and request letter attached to original Form 2 submittal.

The completed portion of the wellbore does not penetrate the described lease but the lease is within the unit.

Distance from completed portion to nearest completed portion of wellbore permitted/completed in the same formation and subject to the proposed spacing order measured to the proposed Drake 3X-HNB-11-07-67 at 300'. Distance measured in 3D anti-collision.

Distance to nearest wellbore belonging to another operator measured to the Lindblad 1-12 (PA, Hrubetz Oil Company, 05-123- 11263) at 1220'. There are no other operator wells with treated interval less 175' from the treated interval of the proposed well. Distances measured in 2D map view.

This application is in a Comprehensive Drilling Plan ☐ No ☐ CDP #: _____

Location ID: 454899

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JENNIFER LIND

Title: VP REG & ENV

Date: 4/21/2020

Email: JENNIFER.LIND@NICKELRO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____

Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05 123 46775 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

Best Management Practices

No BMP/COA Type

Description

1	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
2	Drilling/Completion Operations	Alternative Logging Program: An existing well on the pad was logged with open-hole resistivity log with gamma-ray log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall state "Alternative Logging Program - No open-hole logs were run", and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.
3	Drilling/Completion Operations	Operator acknowledges and will comply with COGCC policy for Bradenhead Monitoring during Hydraulic Fracturing treatments in the Greater Wattenberg Area dated May 29, 2012.

Total: 3 comment(s)

Attachment Check List

Att Doc Num

Name

402376025	OffsetWellEvaluations Data
-----------	----------------------------

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Most current version of the alternative logging program BMP should be used. Return to draft.	04/22/2020

Total: 1 comment(s)



Public Comments

No public comments were received on this application during the comment period.

