

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

402263407

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10459

2. Name of Operator: EXTRACTION OIL & GAS INC

3. Address: 370 17TH STREET SUITE 5300

City: DENVER State: CO Zip: 80202

4. Contact Name: Elaine Winick

Phone: (970) 576-3461

Fax: (970) 534-6001

Email: ewinick@extractionog.com

5. API Number 05-014-20751-00

7. Well Name: Livingston

8. Location: QtrQtr: NWSE Section: 7 Township: 1S Range: 68W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

6. County: BROOMFIELD

Well Number: S19-25-7N

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 12/03/2019 End Date: 12/20/2019 Date of First Production this formation: 04/18/2020
Perforations Top: 8615 Bottom: 20990 No. Holes: 1441 Hole size: 40/100

Provide a brief summary of the formation treatment:

Open Hole: ☐

Frac'd Niobrara with 61 stage plug and perf:
12200035 total pounds 40/70 mesh proppant pumped.
292734 total bbls fluid pumped: 268074 bbls gelled fluid; 24660 bbls fresh water and 0 bbls Acid.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 292734

Max pressure during treatment (psi): 9332

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.33

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.84

Total acid used in treatment (bbl): 0

Number of staged intervals: 61

Recycled water used in treatment (bbl): 0

Flowback volume recovered (bbl): 18555

Fresh water used in treatment (bbl): 24660

Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 12200035

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 04/27/2020 Hours: 24 Bbl oil: 477 Mcf Gas: 944 Bbl H2O: 796
Calculated 24 hour rate: Bbl oil: 477 Mcf Gas: 944 Bbl H2O: 796 GOR: 1979
Test Method: flowing Casing PSI: 2891 Tubing PSI: 2100 Choke Size: 18/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1390 API Gravity Oil: 52
Tubing Size: 2 + 3/8 Tubing Setting Depth: 8605 Tbg setting date: 03/19/2020 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

TPZ: 2385 FSL & 2313 FWL

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Elaine Winick

Title: Completions Tech Date: Email ewinick@extractionog.com

Attachment Check List

Att Doc Num **Name**

402386635 WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)