

FORM
5Rev
02/20**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402407612

Date Received:

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10459

Contact Name: Kamrin Stiver

Name of Operator: EXTRACTION OIL & GAS INC

Phone: (720) 9747743

Address: 370 17TH STREET SUITE 5300

Fax:

City: DENVER

State: CO

Zip: 80202

Email: kstiver@extractionog.com

API Number 05-123-50285-00

County: WELD

Well Name: GP Cody Fed

Well Number: 20E-15-2

Location: QtrQtr: NENE Section: 20 Township: 5N Range: 65W Meridian: 6
FNL/FSL FEL/FWL

Footage at surface: Distance: 682 feet Direction: FNL Distance: 1305 feet Direction: FEL

As Drilled Latitude: 40.389987 As Drilled Longitude: -104.682507

GPS Data: GPS Quality Value: 1.8 Type of GPS Quality Value: PDOP Date of Measurement: 04/09/2020

GPS Instrument Operator's Name: D.WIMMER

FNL/FSL

FEL/FWL

** If directional footage at Top of Prod. Zone Dist: 363 feet Direction: FNL Dist: 1386 feet Direction: FEL
Sec: 20 Twp: 5N Rng: 65W

FNL/FSL

FEL/FWL

** If directional footage at Bottom Hole Dist: 308 feet Direction: FNL Dist: 199 feet Direction: FWL
Sec: 22 Twp: 5N Rng: 65W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 01/03/2020 Date TD: 02/11/2020 Date Casing Set or D&A: 02/12/2020

Rig Release Date: 04/06/2020 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 14211 TVD** 6954 Plug Back Total Depth MD 14189 TVD** 6954

Elevations GR 4673 KB 4702

Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

CBL, MUD, MWD, (DUAL INDUCTION 123-24990)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	42	0	80	100	0	80	VISU
SURF	12+1/4	9+5/8	36	0	1,611	590	0	1,611	VISU
1ST	8+1/2	5+1/2	20	0	14,189	2,288	1,920	14,189	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,701		NO	NO	
SUSSEX	4,189		NO	NO	
SHANNON	4,844		NO	NO	
SHARON SPRINGS	6,863		NO	NO	
NIOBRARA	6,890		NO	NO	

Operator Comments:

The TPZ footages are estimates calculated through Directional Plotting Software—from where the production string (5 ½" casing) crosses the 460' setback hardline. The actual footages will be submitted with the Form 5A.
Alternative Logging Program- No open hole resistivity log with gamma ray was run on this well. Resistivity ran on CDOT-2 D7 (123-24990)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kamrin Stiver

Title: Drilling Technician Date: _____ Email: kstiver@extractionog.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
402407826	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
402408188	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
402407822	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402407823	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402407824	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402407825	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402408187	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

