




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Francis Steckel WELL NO. 1

FIELD Pierce WILDCAT — COUNTY Weld

LOCATION SW SW Section 14 Township 8N Range 66W Meridian 6th P. M.

660 feet from S Section Line and 1000 feet from E Section Line

N or S E or W

(DETAILS OF WORK)

This well was penetrated through the Lyons sand to a T.D. of 9360'. The cores and tests indicated that it had no commercial possibilities. Details of these are attached. The following plugging procedure was approved in a phone conversation of September 19, 1957 between Mr. D. V. Rogers and Mr. O. L. Wyble.

- Place 50 sack cement plug over top of Lyons.
- Place 50 sack cement plug over top of Muddy.
- Place 100 sack cement plug over shoe of 10 3/4" casing.
- Place 25 sack cement plug in top of surface casing with usual 4" marker imbedded in same and extending 3' above ground level.

AJJ	
DVR	
FJK	
WKS	
HHA	
AM	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: SEP 23 1957

Date SEP 23 1957

Director A. J. Jersin

Company The California Company Date Sept. 19, 1957

Address P. O. Box 1769, Casper, Wyo. Phone No. 2-5303

By R. J. Dever Title Area Superintendent

(Signature)