




00218991

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other - Plugging Record	<input checked="" type="checkbox"/>

(Check appropriate space)

LEASE NAME Francis Steckel WELL NO. 1

FIELD Pierce WILDCAT COUNTY Weld

LOCATION SW SW Section 14 Township 8N Range 66W Meridian 6th P. M.  
 (Quarter Quarter)

660 feet from S Section Line and 1000 feet from E Section Line  
 N or S E or W

(DETAILS OF WORK)

The subject well was plugged and abandoned on September 20, 1957 in the following manner, as approved by Mr. D. V. Rogers in phone conversation of September 19, 1957.

1. Placed 50 sacks Slo-set cement, balanced plug across top of Lyons from 9129'-9291' (Top Lyons - 9274')
2. Placed 50 sacks Slo-Set cement balanced plug across top of Muddy from 7813'-7975' (Top Muddy - 7990')
3. Placed 100 sacks regular cement, containing 1% CaCl<sub>2</sub>, balanced plug across shoe of surface pipe 273' - 654'.
4. Placed 25 sacks regular cement plug in top of surface pipe. A 4" pipe for a marker was embedded in cement in top of surface pipe and extends 3' above ground level. The 9 5/8" Surface Casing was landed at 411'.

The subject well was drilled to a total depth of 9360'.

AJJ	
DVR	
FJK	
WIC	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

SEP 25 1957

Date SEP 25 1957  
Director A. J. Jersin

Company The California Company Date Sept. 23, 1957

Address P. O. Box 1769, Casper, Wyo. Phone No. 2-5303

By [Signature] Title Area Supt.

(Signature)