

FORM
6Rev
02/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402471153

Date Received:

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 47120

Contact Name: CANDICE BARBER

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (307) 233-4513

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

Email: CANDICE_BARBER@OXY.COM

For "Intent" 24 hour notice required,

Name:

Tel:

COGCC contact:

Email:

Type of Well Abandonment Report: ☐ Notice of Intent to Abandon ☒ Subsequent Report of Abandonment

API Number 05-123-15674-00

Well Name: HSR-WILDER

Well Number: 15-8A

Location: QtrQtr: SWSE Section: 8 Township: 3N Range: 66W Meridian: 6

County: WELD

Federal, Indian or State Lease Number:

Field Name: WATTENBERG

Field Number: 90750

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.233888

Longitude: -104.798970

GPS Data: GPS Quality Value: 1.5 Type of GPS Quality Value: PDOP Date of Measurement: 07/28/2020

GPS Instrument Operator's Name: PAT MCCLURE

Reason for Abandonment: ☐ Dry ☐ Production Sub-economic ☐ Mechanical Problems☐ OtherCasing to be pulled: ☐ Yes ☐ No Estimated Depth:Fish in Hole: ☐ Yes ☐ No If yes, explain details belowWellbore has Uncemented Casing leaks: ☐ Yes ☐ No If yes, explain details below

Details:

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7388	7406	03/13/2020	B PLUG CEMENT TOP	7030
NIOBRARA	7102	7268	03/13/2020	B PLUG CEMENT TOP	7030
J SAND	7848	7890	03/13/2020	B PLUG CEMENT TOP	7440

Total: 3 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	463	330	463	0	VISU
1ST	7+7/8	4+1/2	11.6	7,528	140	7,528	6,651	CBL
1ST LINER	3+7/8	2+7/8	6.5	7,967	25	7,967	7,500	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 7440 with 2 sacks cmt on top. CIBP #2: Depth 7030 with 2 sacks cmt on top.

CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.

CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 50 sks cmt from 629 ft. to 557 ft. Plug Type: OPEN HOLE Plug Tagged: ☒

Set 100 sks cmt from 557 ft. to 410 ft. Plug Type: CASING Plug Tagged: ☒

Set 132 sks cmt from 410 ft. to 30 ft. Plug Type: CASING Plug Tagged: ☒

Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at 1200 ft. with 187 sacks. Leave at least 100 ft. in casing 860 CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set _____ sacks half in. half out surface casing from _____ ft. to _____ ft. Plug Tagged: ☐

Set 11 sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☒ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 623 ft. of 8+5/8 inch casing Cut and Cap Date: 07/28/2020

*Wireline Contractor: RELIANCE *Cementing Contractor: BASIC

Type of Cement and Additives Used: _____

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☐ No

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CANDICE BARBER

Title: REGULATORY ANALYST Date: _____ Email: DJPOSTDRILL@ANADARKO.COM

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY:

COA Type **Description**

Attachment Check List

Att Doc Num

Name

402471212	WELLBORE DIAGRAM
402471216	OTHER
402471220	CEMENT JOB SUMMARY
402471235	WIRELINER JOB SUMMARY
402471247	OPERATIONS SUMMARY

Total Attach: 5 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	------------------------

Total: 0 comment(s)