







APPROXIMATE CUTTINGS VOLUME	
	CU. YDS.
CUTTINGS AREA	±10,840
ADDITIONAL CUTTINGS (3' HIGH)	±2,090
ADDITIONAL CUTTINGS ON WELL PAD CUT SLOPE (IF STACKABLE)	±5,890
<b>TOTAL CUTTINGS</b>	<b>±18,820</b>

APPROXIMATE EARTHWORK QUANTITIES	
(6") TOPSOIL STRIPPING	5,960 Cu. Yds.
REMAINING LOCATION	54,570 Cu. Yds.
CUTTINGS AREA	10,840 Cu. Yds.
<b>TOTAL CUT</b>	<b>71,370 Cu. Yds.</b>
<b>FILL</b>	<b>49,940 Cu. Yds.</b>
EXCESS MATERIAL	21,430 Cu. Yds.
TOPSOIL & AREA BACKFILL	16,800 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>4,630 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±10.615
30' WIDE ACCESS ROAD R-O-W DISTURBANCE	±185'	±0.127
30' WIDE SECONDARY ACCESS ROAD R-O-W DISTURBANCE	±842'	±0.580
TOTAL SURFACE USE AREA		±11.322

REV: 8	08-11-20	T.L.L.	(ADD WELL NAMES)
--------	----------	--------	------------------

**BJU B26 496 PAD**  
**NE 1/4 NW 1/4, SECTION 26, T4S, R96W, 6th P.M.**  
**GARFIELD COUNTY, COLORADO**

<b>SURVEYED BY</b>	DAYTON SLAUGH, K.H.	03-09-20	<b>SCALE</b>
<b>DRAWN BY</b>	T.L.L.	03-13-20	AS SHOWN
<b>CONSTRUCTION LAYOUT CROSS SECTIONS</b>			<b>FIGURE #2</b>

**NOTES:**

- Fill quantity includes 20% for compaction.
- Calculations based on 6" of topsoil stripping.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted).
- All calculations done assuming cuttings are "stackable".



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017