

FORM  
2

Rev  
02/20

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402470888

**(SUBMITTED)**

Date Received:

## APPLICATION FOR PERMIT TO:

Drill       Deepen       Re-enter       Recomplete and Operate

TYPE OF WELL OIL  GAS  COALBED  OTHER: \_\_\_\_\_

Refilling

ZONE TYPE SINGLE ZONE  MULTIPLE ZONES  COMMINGLE ZONES

Sidetrack

Well Name: Schuh 3-65 21-20 Well Number: 4AH  
 Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC COGCC Operator Number: 10633  
 Address: 1801 CALIFORNIA STREET #2500  
 City: DENVER State: CO Zip: 80202  
 Contact Name: Kathy Denzer Phone: (720)410-8519 Fax: ( )  
 Email: Kathy.Denzer@crestonepr.com

## RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160104

## WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 21 Twp: 3S Rng: 65W Meridian: 6  
 Latitude: 39.772476 Longitude: -104.661139  
 Footage at Surface: 1248 Feet FNL/FSL 475 Feet FEL/FWL FEL  
 Field Name: WILDCAT Field Number: 99999  
 Ground Elevation: 5597 County: ADAMS  
 GPS Data: GPS Quality Value: 1.2 Type of GPS Quality Value: PDOP Date of Measurement: 11/08/2017  
 Instrument Operator's Name: Chad Meiers  
 If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**  
 Footage at Top of Prod Zone: FNL/FSL 1096 FSL 330 FEL 1111 FSL 330 FEL/FWL FWL  
 Sec: 21 Twp: 3S Rng: 65W Sec: 20 Twp: 3S Rng: 65W

## LOCAL GOVERNMENT INFORMATION

County: ADAMS Municipality: Aurora

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: Municipality

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below.  Yes  No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The local government siting permit type is: Site Plan

The local government siting permit was filed on: 03/01/2018

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

The Site Plan was approved on 6/6/18.

## LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:  Fee  State  Federal  Indian

The Surface Owner is:  is the mineral owner beneath the location.

(check all that apply)

is committed to an Oil and Gas Lease.

has signed the Oil and Gas Lease.

is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:  Fee  State  Federal  Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Please see lease map in well file.

Total Acres in Described Lease: 860 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building:	<u>1658</u> Feet
Building Unit:	<u>1930</u> Feet
High Occupancy Building Unit:	<u>5280</u> Feet
Designated Outside Activity Area:	<u>5280</u> Feet
Public Road:	<u>475</u> Feet
Above Ground Utility:	<u>449</u> Feet
Railroad:	<u>5280</u> Feet
Property Line:	<u>475</u> Feet
School Facility:	<u>5280</u> Feet
School Property Line:	<u>5280</u> Feet
Child Care Center:	<u>5280</u> Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

### DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:  Buffer Zone  Exception Zone  Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

### SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 680 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 330 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

### SPACING & FORMATIONS COMMENTS

\_\_\_\_\_

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: \_\_\_\_\_

### OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1265	1280	Sec. 20 and 21: All

### DRILLING PROGRAM

Proposed Total Measured Depth: 18288 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: \_\_\_\_\_ Feet  No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H2S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H2S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

### GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

### DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: \_\_\_\_\_ Drilling Fluids Disposal Methods: \_\_\_\_\_

Cuttings Disposal: \_\_\_\_\_ Cuttings Disposal Method: \_\_\_\_\_

Other Disposal Description:

Drilling cuttings will be taken by a certified transport company and disposed of at a certified facility.

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	100	0	100	0
SURF	13+1/2	9+5/8	36	0	2188	977	2188	0
1ST	8+1/2	5+1/2	23	0	18288	2663	18288	

Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

- Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments: Distance to nearest wellbore permitted or completed in the same formation was measured in 2D to the proposed Schuh 3-65 21-20 4BH.

Changes to the original APD are top of productive zone, bottom hole and casing and cement program (approved on a Form 4 with Document Number 402370393) and measured depth. All attachments remain the same as the original APD or approved Form 4 that was approved on 04/28/20.

The location has been built and has one well drilled.

This application is in a Comprehensive Drilling Plan       No       CDP #: \_\_\_\_\_

Location ID:       457713      

Is this application being submitted with an Oil and Gas Location Assessment application?       No      

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name:       Andrea Gross      

Title:       Permit Agent       Date: \_\_\_\_\_ Email:       agross@upstreampm.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

<b>API NUMBER</b>
05 001 10200 00

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

<u>COA Type</u>	<u>Description</u>



## Best Management Practices

<b>No</b>	<b>BMP/COA Type</b>	<b>Description</b>
1	Drilling/Completion Operations	Prior to drilling operations, Crestone will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, the Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as constructed gyro survey will be submitted to COGCC with the Form 5.
2	Drilling/Completion Operations	Crestone will comply with the COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
3	Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measuredwhiledrilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without openhole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which openhole logs were run.
4	Drilling/Completion Operations	No drill stem tests will be performed.
5	Drilling/Completion Operations	Backup stabbing valves shall be required on well servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using both low-pressure air and high-pressure fluid.
6	Drilling/Completion Operations	Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections will be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results will be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.
7	Drilling/Completion Operations	Neosteer CL a rotary steerable unit that reduces drilling time on-site will be used. Additionally, mud chillers will be used to control cuttings odor while drilling through hydrocarbon bearing zones.
8	Drilling/Completion Operations	Adequate blowout prevention equipment will be used on all well servicing operations.

Total: 8 comment(s)

## Attachment Check List

<b>Att Doc Num</b>	<b>Name</b>
402478184	OffsetWellEvaluations Data

Total Attach: 1 Files

## General Comments

<b>User Group</b>	<b>Comment</b>	<b>Comment Date</b>
		Stamp Upon Approval

Total: 0 comment(s)

**Public Comments**

No public comments were received on this application during the comment period.

