

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
402480927
Receive Date:
09/02/2020
Report taken by:
RICK ALLISON

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation. Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers
Address: 1001 NOBLE ENERGY WAY		Phone: (970) 3045329
City: HOUSTON State: TX Zip: 77070		Mobile: ()
Contact Person: Jacob Evans	Email: jacob.evans@nblenergy.com	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION
Remediation Project #: 13496 Initial Form 27 Document #: 402029641

PURPOSE INFORMATION

<input type="checkbox"/> 901.e. Sensitive Area Determination	<input checked="" type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water
<input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure	<input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b.
<input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation	<input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project
<input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste	<input type="checkbox"/> Rule 906.c.: Director request
<input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure	<input type="checkbox"/> Other

SITE INFORMATION Y Multiple Facilities (in accordance with Rule 909.c.)

Facility Type: LOCATION	Facility ID: 328608	API #: _____	County Name: WELD
Facility Name: SPIKE STATE-64N63W 6NWSW	Latitude: 40.339426	Longitude: -104.487773	
** correct Lat/Long if needed: Latitude: 40.337821		Longitude: -104.489289	
QtrQtr: NWSW Sec: 6 Twp: 4N Range: 63W Meridian: 6	Sensitive Area? Yes		
Facility Type: SPILL OR RELEASE	Facility ID: 471228	API #: _____	County Name: WELD
Facility Name: Spike State CC 6-12	Latitude: 40.337821	Longitude: -104.489289	
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: NWSW Sec: 6 Twp: 4N Range: 63W Meridian: 6	Sensitive Area? Yes		

SITE CONDITIONS

General soil type - USCS Classifications SW Most Sensitive Adjacent Land Use Various

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? No

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Occupied Building 900'

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> E&P Waste | <input type="checkbox"/> Other E&P Waste | <input type="checkbox"/> Non-E&P Waste |
| <input checked="" type="checkbox"/> Produced Water | <input type="checkbox"/> Workover Fluids | _____ |
| <input checked="" type="checkbox"/> Oil | <input type="checkbox"/> Tank Bottoms | |
| <input checked="" type="checkbox"/> Condensate | <input type="checkbox"/> Pigging Waste | |
| <input type="checkbox"/> Drilling Fluids | <input type="checkbox"/> Rig Wash | |
| <input type="checkbox"/> Drill Cuttings | <input type="checkbox"/> Spent Filters | |
| | <input type="checkbox"/> Pit Bottoms | |
| | <input type="checkbox"/> Other (as described by EPA) | _____ |

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	20' X 13'	Laboratory Analytical
Yes	SOILS	20' X 13' X 6' BGS	Laboratory Analytical

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

During decommissioning operations at the Spike State CC6-12,13,14,11J facility crews discovered soil impacts in the vicinity of the produced water vault due to a historical release.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Four grab soil samples were collected by Eagle Environmental for analysis of TPH-DRO by EPA Method 8015D, TPH-GRO, BTEX, and Naphthalene by EPA Method 8260C. Additionally, SS-01@3' was analyzed for EC by Modified 9050A, pH by EPA 9045D, and SAR by 20B Saturated Paste.

Proposed Groundwater Sampling

Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

One grab groundwater sample was collected by Eagle Environmental at the base of the excavation for analysis of BTEX by EPA Method 8260C.

Proposed Surface Water Sampling

Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 4
Number of soil samples exceeding 910-1 1
Was the areal and vertical extent of soil contamination delineated? No
Approximate areal extent (square feet) 260

NA / ND

-- Highest concentration of TPH (mg/kg) 799
-- Highest concentration of SAR 3.15
BTEX > 910-1 No
Vertical Extent > 910-1 (in feet) 6

Groundwater

Number of groundwater samples collected 1
Was extent of groundwater contaminated delineated? No
Depth to groundwater (below ground surface, in feet) 6'
Number of groundwater monitoring wells installed 0
Number of groundwater samples exceeding 910-1 1

-- Highest concentration of Benzene (µg/l) 14.5
ND Highest concentration of Toluene (µg/l)
-- Highest concentration of Ethylbenzene (µg/l) 370
-- Highest concentration of Xylene (µg/l) 610
NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected
 Number of surface water samples exceeding 910-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

Were impacts to adjacent property or offsite impacts identified?

Were background samples collected as part of this site investigation?

Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) Volume of liquid waste (barrels)

Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No _____

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

The source was removed from February 27-28, 2020 through excavation of impacted soil above COGCC standards. Eagle Environmental was on location to field guide the excavation and collect grab confirmation soil samples above the phreatic zone. All soil samples were delivered under standard chain of custody procedures to a certified laboratory for analysis of TPH-DRO, TPH-GRO, BTEX, and Naphthalene.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Six groundwater monitoring wells were installed and will be sampled on a quarterly basis to monitor for natural attenuation. Once four consecutive quarters of COGCC compliant groundwater is achieved a no further action request will be submitted.

Soil Remediation Summary

In Situ

Ex Situ

_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Air sparge / Soil vapor extraction
_____ Natural Attenuation
_____ Other _____

Yes _____ Excavate and offsite disposal
If Yes: Estimated Volume (Cubic Yards) _____ 800
Name of Licensed Disposal Facility or COGCC Facility ID # _____
No _____ Excavate and onsite remediation
_____ Land Treatment
_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Other _____

Groundwater Remediation Summary

No _____ Bioremediation (or enhanced bioremediation)
No _____ Chemical oxidation
No _____ Air sparge / Soil vapor extraction
Yes _____ Natural Attenuation
Yes _____ Other A groundwater amendment was placed at the base of the excavation to aid in groundwater remediation _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Six groundwater monitoring wells were installed to delineate dissolved phase groundwater impacts. These wells will be sampled on a quarterly basis and the groundwater samples will be analyzed by a certified laboratory for analysis of BTEX by EPA Method 8260c.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: Quarterly Semi-Annually Annually Other _____

Report Type: Groundwater Monitoring Land Treatment Progress Report O&M Report

Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes _____

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use

Volume of E&P Waste (solid) in cubic yards _____ 800

E&P waste (solid) description E&P solid waste derived from excavation activities _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: Buffalo Ridge Landfill _____

Volume of E&P Waste (liquid) in barrels _____ 80

E&P waste (liquid) description E&P liquid waste derived from excavation activities. _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: NGL C6 _____

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No _____

Do all soils meet Table 910-1 standards? Yes _____

Does the previous reply indicate consideration of background concentrations? No _____

Are the only residual soil impacts pH, SAR, or EC at depths greater than 3 feet below ground surface? _____

Does Groundwater meet Table 910-1 standards? Yes _____

Is additional groundwater monitoring to be conducted? Yes _____

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Reclamation will be in accordance with COGCC 1000 series rules.

Is the described reclamation complete? No _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

Interim? Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. _____

Actual Spill or Release date, if known. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 02/06/2020

Date of commencement of Site Investigation. _____

Date of completion of Site Investigation. 02/06/2020

REMEDIAL ACTION DATES

Date of commencement of Remediation. 02/27/2020

Date of completion of Remediation. _____

SITE RECLAMATION DATES

Date of commencement of Reclamation. 02/06/2020

Date of completion of Reclamation. _____

OPERATOR COMMENT

--

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Jacob Evans

Title: Environmental Coordinator

Submit Date: 09/02/2020

Email: jacob.evans@nblenergy.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: RICK ALLISON

Date: 09/03/2020

Remediation Project Number: 13496

COA Type

Description

<u>COA Type</u>	<u>Description</u>

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num

Name

402480927	FORM 27-SUPPLEMENTAL-SUBMITTED
402480933	MONITORING REPORT

Total Attach: 2 Files

General Comments

User Group

Comment

Comment Date

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)