

FORM  
2

Rev  
02/20

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402448187

(SUBMITTED)

Date Received:

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: \_\_\_\_\_

Refilling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Blue Teal Fed

Well Number: 15-3-7HN

Name of Operator: MALLARD EXPLORATION LLC

COGCC Operator Number: 10670

Address: 1400 16TH STREET SUITE 300

City: DENVER

State: CO

Zip: 80202

Contact Name: Erin Mathews

Phone: (720)543 7951

Fax: ( )

Email: emathews@mallardexploration.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20170115

WELL LOCATION INFORMATION

QtrQtr: NWNE Sec: 22 Twp: 8N Rng: 60W Meridian: 6

Latitude: 40.653832

Longitude: -104.075447

Footage at Surface: 480 Feet FNL/FSL FNL 2127 Feet FEL/FWL FEL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 4892

County: WELD

GPS Data: GPS Quality Value: 1.7 Type of GPS Quality Value: PDOP Date of Measurement: 08/09/2017

Instrument Operator's Name: Ian Carabajal

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL

300 FSL 1635 FEL 1721 FSL 1635 FEL

Sec: 15 Twp: 8N Rng: 60W Sec: 3 Twp: 8N Rng: 60W

LOCAL GOVERNMENT INFORMATION

County: WELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below. ☒ Yes ☐ No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☒

The local government siting permit type is: WOGLA

The local government siting permit was filed on: 04/22/2019

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

WOGLA19-0061 submitted 4/22/2019, Approved 8/16/2019.

## LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

SE/4, 15, 8N, 60W

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 2121 Feet

Above Ground Utility: 2088 Feet

Railroad: 5280 Feet

Property Line: 480 Feet

School Facility: 5280 Feet

School Property Line: 5280 Feet

Child Care Center: 5280 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 671 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 300 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: \_\_\_\_\_

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1325	3200	9N:27,34; 8N:3,10,15

## DRILLING PROGRAM

Proposed Total Measured Depth: 18629 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 352 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	43	0	80	50	80	0
SURF	13+1/2	9+5/8	36	0	1550	525	1550	0
1ST	8+1/2	5+1/2	20	0	18629	2675	18629	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

This Form 2 is being submitted as a refile of API 05-123-48427 formerly known as Blue Teal Fed 15-10-13HN.

This is part of a multi-pad realignment to maximize efficiency and decrease number and acreage of surface disturbance for wells under Order 535-1325 covering Sections 27 & 34 of 9N-60W and the Sections 3, 10, & 15 of 8N-60W.

The PT-1 (API: 05-123-46553) to be known as Pintail Fed 3-15-9HN will be renamed and adjusted to extend into Sections 15, 10, and 3 with revised TPZ and BHL to meet setbacks in accordance with proposed spacing amendments within approved Order 535-1325. The SHL will move within the Pintail Pad (Loc ID 454414) for engineering purposes. Sundry Doc #402449282 is being submitted for the Pintail Pad location to update the Cultural Distances and multi-well plan.

The Blue Teal 15-10-1HN (API: 05-123-48426) to be known as Blue Teal Fed 15-3-1HN, Blue Teal 15-10-3HN (API: 05-123-48417) to be known as Blue Teal Fed 15-3-2HN, Blue Teal 15-10-5HN (API: 05-123-48425) to be known as Blue Teal Fed 15-3-3HN, Blue Teal 15-10-7HN (API: 05-123-48414) to be known as Blue Teal Fed 15-3-4HC, Blue Teal 15-10-8HN (API: 05-123-48423) to be known as Blue Teal Fed 15-3-5HN, Blue Teal Fed 15-10-11HC (API: 05-123-48415) to be known as Blue Teal Fed 15-3-6HN, Blue Teal Fed 15-10-13HN (API: 05-123-48427) to be known as Blue Teal Fed 15-3-7HN, Blue Teal Fed 15-10-15HC (API: 05-123-48420) to be known as Blue Teal Fed 15-3-8HN, and Blue Teal Fed 15-10-16HN (API: 05-123-48424) to be known as Blue Teal Fed 15-3-9HN will be renamed, extended, and respaced and across Sections 15, 10, and 3 with revised TPZ and BHL to meet setbacks in accordance with proposed spacing amendments within Order 535-1325.

The Blue Teal 15-10-2HC (API: 05-123-48413), Blue Teal 15-10-4HN (API: 05-123-48416), Blue Teal 15-10-6HC (API: 05-123-48428), Blue Teal Fed 15-10-9HN (API: 05-123-48421), Blue Teal Fed 15-10-10HN (API: 05-123-48419), Blue Teal Fed 15-10-12HN (API: 05-123-48422), and Blue Teal Fed 15-10-14HN (API: 05-123-48418) are being abandoned from the location.

The Rouen Pad (Loc ID 466757) is being abandoned along with its associated 14 Wells (05-123-50389, 05-123-50390, 05-123-50391, 05-123-50392, 05-123-50393, 05-123-50394, 05-123-50395, 05-123-50396, 05-123-50397, 05-123-50398, 05-123-50399, 05-123-50400, 05-123-50401, 05-123-50402).

There have been no new buildings constructed and no changes to the surrounding land use and mineral lease description. The SHL of the existing wells have been adjusted slightly within the proposed disturbance. The well site has not yet been constructed. This location is not in a buffer or exception zone, so no notices are required under Rule 305. All previously submitted notices, Surface Use Agreements, and letters are also still valid. Sundry Doc #402448189 is being submitted for the Blue Teal Pad location to update the equipment and multi-well plan.

The nearest well in information has been updated to reflect the respaced laterals.

Nearest well in unit per anti-collision is the Blue Teal Fed 15-3-6HN.

Nearest outside operated well per anti-collision is the Badger Federal LF 03-64HN (API: 05-123-34384) PR Status.

This application is in a Comprehensive Drilling Plan No CDP #: \_\_\_\_\_

Location ID: 458635

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Justin Garrett

Title: Regulatory Analyst Date: \_\_\_\_\_ Email: regulatory@ascentgeomatics.c

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

**API NUMBER**

05 123 48427 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

## Best Management Practices

### No BMP/COA Type

### Description

1	Drilling/Completion Operations	Blowout Prevention Equipment ("BOPE"): A double ram annular preventer will be used during drilling.
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
3	Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on the pad will be logged with an open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a Cement Bond Log with Gamma-Ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.

Total: 3 comment(s)

## Attachment Check List

### Att Doc Num

### Name

402479797	SURFACE AGRMT/SURETY
402485075	DEVIATED DRILLING PLAN
402485077	DIRECTIONAL DATA
402485078	WELL LOCATION PLAT
402487432	OffsetWellEvaluations Data

Total Attach: 5 Files

## General Comments

### User Group

### Comment

### Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)

## Public Comments

No public comments were received on this application during the comment period.

